

**Kourosh  
Mehin/DPI/VICGOV1**  
02/06/2008 09:09 AM

To Michael Holbrook/DPI/VICGOV1@VICGOV1  
cc  
bcc  
Subject Fw: Amendment to East Wing-1 drilling programme

Michael  
Please for your record.  
KM  
Regards

Kourosh Mehin

-----  
**Dr Kourosh Mehin**  
Principal Petroleum Resources Advisor  
Tel.: (61 3) 9658 4416  
Fax.: (61 3) 9658 4499  
  
Mobile: 0419 597 010

----- Forwarded by Kourosh Mehin/DPI/VICGOV1 on 02/06/2008 09:08 AM -----



**"Geoff Rowlands"**  
<knaphill@aapt.net.au>  
01/06/2008 11:51 AM

To <terry.mckinley@dpi.vic.gov.au>  
cc <david.wong@dpi.vic.gov.au>, <kourosh.mehin@dpi.vic.gov.au>, "John Remfry" <jremfry@eprl.com.au>, "Gordon Wakelin-King" <gwakelin@eprl.com.au>, "Jim Slater" <jimslater@kdc.net.au>, <lourig5@bigpond.com>  
Subject RE: Amendment to East Wing-1 drilling programme

Dear Terry,

Further to Gordon Wakelin-King's email yesterday, I attach the proposed well schematic for the suspension of East Wing-1ST.

Regards,

Geoff Rowlands

Pp Gordon Wakelin-King  
Essential Petroleum Resources Limited  
Essential Petroleum Exploration Pty Ltd

---

**From:** Gordon Wakelin-King [mailto:gwakelin@eprl.com.au]  
**Sent:** Saturday, 31 May 2008 7:50 PM  
**To:** terry.mckinley@dpi.vic.gov.au  
**Cc:** david.wong@dpi.vic.gov.au; kourosh.mehin@dpi.vic.gov.au; jremfry@eprl.com.au; knaphill@aapt.net.au  
**Subject:** Amendment to East Wing-1 drilling programme

Dear Terry

Essential Petroleum wishes to advise that two attempts to evaluate gas zone(s) in the East Wing-1 sidetrack well by wireline techniques (MFT pressure sampling) has been unsuccessful due to ongoing hole conditions. Logging tools cannot pass hole obstructions despite running wiper trips. An open hole DST in the present hole would be inadvisable due to the extreme risk of becoming stuck in the hole. Essential Petroleum proposes to secure the well by casing and suspending.

A diagram of the proposed casing program will be provided shortly under separate cover. I can advise that the cement program includes a sufficient cement rise in the annulus to overlap the shoe of the surface casing at 578m.

As testing of the potential gas zones has not been possible we are unable to advise a final completion program at this time. At a future date EPR will make application to test the well through perforated casing, and will provide a detailed program to accompany that application.

The casing program will most likely commence late on Sunday 1 June.

Best regards

Gordon Wakelin-King  
Essential Petroleum Resources Limited



Essential Petroleum Exploration Pty Ltd [East Wing-1ST Suspension Diagram Pre Completion.XLS](#)