

WCR (BASIC DATA) VOLUME 1 OF 2 WHIPTAIL-1A (W915)

ESSO EXPLORATION AND PRODUCTION AUSTRALIA INC.

OIL and GAS DIVISION
WELL COMPLETION REPORT
WHIPTAIL-1A
BASIC DATA
VOLUME I 27 MAR 1986

GIPPSLAND BASIN VICTORIA

ESSO AUSTRALIA LIMITED

Compiled by: P.A.ARDITTO

WHIPTAIL-1A

WELL COMPLETION REPORT

VOLUME 1

CONTENTS

1.	Well Data Record
2.	Operations Summary
3.	Casing Data
4.	Cement Data
5.	Samples, Conventional Cores, Sidewall Cores
6.	Wireline Logs and Surveys
7.	RFT Pressure Data
8.	Temperature Record

FIGURES

1.	Locality Map
2.	Well Progress Curve
3.	Well Bore Schematic
4.	Abandonment Schematic
5.	Horner Temperature Plot

APPENDICES

1.	Lithological Descriptions
2.	Core Descriptions
3.	Sidewall Core Descriptions
4.	Sidewall Core Gas Analysis
5.	RFT Results
6.	Velocity Survey Report

1096L/12

ESSO AUSTRALIA LTD

1. WELL DATA RECORD

WELL : WHIPTAIL-1A

LOCATION : Latitude : 380 19' 30.351" S

Longitude : 1470 31' 09.587" E

X = 545,394.04 mE Y = 5,757,971.49 mN

Map Projection: AMG ZONE 55 CM 1470 E

Geographical Location: Bass Strait Victoria

Field: WHIPTAIL

PERMIT : Vic/Ll

ELEVATION : 21m KB

WATER DEPTH : 39m

TOTAL DEPTH : 2821m KB (2800 mSS)

PLUG BACK TYPE : Balanced cement plug

REASONS FOR

PLUGGING BACK : Well suspended

MOVE IN : 04:15 hrs., August 6, 1985

SPUDDED : 01:45 hrs., August 10, 1985

REACHED T.D. : August 28, 1985

RIG RELEASED : 04:45 hrs., September 4, 1985

OPERATOR : Esso Exploration and Production Australia Inc.

PERMITTEE OR LICENCEE : BHP Petroleum Pty. Ltd. & EEPA

ESSO INTEREST : 50%

OTHER INTEREST : 50%

CONTRACTOR : South Seas Drilling Company

RIG NAME : Southern Cross

EQUIPMENT TYPE : Semi submersible

TOTAL RIG DAYS : 30

DRILLING AFE NO. : 05-235009

TYPE COMPLETION : Plugged cased and Suspended

WELL CLASSIFICATION : Before Drilling New field Wildcat

After Drilling New field discovery.

1848L/27

2. OPERATIONS SUMMARY WHIPTAIL-I

MOVING/MOORING

The Southern Cross departed the Snapper-5 well location at 2115 hrs, August 5, 1985 and arrived at the Whiptail-1 location at 0415 hrs, August 6, 1985. The workboat, Lady Sally, towed the rig 25 nautical miles in 7 hours at an average speed of 3.6 knots.

While approaching the well location, the rig dropped the No. 1 anchor. The remaining seven anchors were run by the Swan Tide and Torrens Tide. The No. 1 anchor was pulled and its flukes cleared of a fouled pendant line after all but anchor No. 6 had been run.

Before deployment, Anchor No. 7 was fitted with a Baldt detachable chain chaser and used to test the feasibility of a chain chaser on a wire and chain mooring system. Due to unfamiliarity with the chain chaser, the workboat, Torrens Tide, made two trips to set the anchor.

All anchors were run in 12 hours and pretensioned to 230 kips.

Final Rig Location

Latitude : 380 19' 30.391"S Longitude : 1470 31' 10.327"E

X: 545,412mE Y: 5,757,970mN

AMG Zone 55, Universal Transverse Mercator Projection, Australian Geodetic Datum.

The rig was located 1.85m at $180^{\rm O}$ from the called location and approximately 70km southwest of Lakes Entrance, Victoria.

DRILL 26" HOLE FOR 20" CASING

The drilling template was run and landed at a seafloor depth of 61mRKB. The 26" hole was drilled to 198m using seawater and high viscosity gel slugs to clean the hole. A wiper trip was conducted and the hole displaced with high viscosity mud prior to pulling the bit to run casing. The 18-3/4" pile joint assembly and 20" casing were run and cemented with the casing shoe at 180m.

After the BOP stack and riser were run, the pressure test on the casing and collet connector failed. Divers observed a leak in the casing annulus. Oper ended drillpipe tagged cement inside the casing at 91m.

Due to the leak in the casing, the BOP stack was pulled and the 20" casing mechanically cut. The pile joint assembly, four post guidebase and drilling template were retrieved. On surface, the "CC" connector between the pile joint assembly and 20" casing crossover joint was inspected and found missing its 0-ring.

WHIPTAIL-1A

MOVE

The rig was winched approximately 18m at 2730 from the Whiptail-1 location.

Final Rig Location

Latitude : 380 19' 30.351"S Longitude : 1470 31' 09.587"E

X: 545,394mE Y: 5,757,971mN

AMG Zone 55, Universal Transverse Mercator Projection, Australian Geodetic Datum

DRILL 26" HOLE FOR 20" CASING

The drilling template was run and landed at a seafloor depth of 60mRKB. The 26" hole was drilled to 197m and the 20" casing run and cemented at 182m in the same manner as in the Whiptail-l well. The BOP stack was run and the collet connector and casing tested to 500psi.

17-1/2" HOLE FOR 13-3/8" CASING

Cement inside the 20" casing was tagged at 173m and drilled out along with new hole to a depth of 797m. High viscosity gel pills were pumped every third connection to 350m. While POH at TD, tight hole was experienced from 779 to 72lm and singles had to be pumped out from 72l to 550m. After running back to bottom and washing 6m of fill, no further hole problems occurred.

The hole was logged and 13-3/8" casing was run and cemented at 782m. The plug was bumped with 1600 psi. A Cameron 13-3/8" Weight Set seal assembly was run and pressure tested to 200/5000psi. The BOP stack was then tested.

DRILL 12-1/4" HOLE TO 2821m

After drilling out the float collar and cement below the lowest casing connection, the casing was pressure tested to 1500psi. The remaining cement and new hole was drilled to 803m before a casing shoe PIT was run to leakoff at 500psi (12.4ppg EMW at casing shoe).

The 12-1/4" hole was drilled to 1165.4m using a seawater gel mud system. The mud weight was gradually increased from 8.8ppg to 10.3ppg over the interval 94lm to 1062m. The mud weight was increased so that a 300psi overbalance would be present before penetrating a predicted 36m gas column in the top of the "Coarse Clastics".

At 1165.4m, an open hole PIT was run to leakoff at 400psi (13.3ppg EMW at casing shoe) before the bit was pulled. Core No. 1 was cut from 1165.4 to 1175.4m. The 12-1/4" hole was drilled to the original TD of 202lm. The mud weight was dropped from 10.3ppg to 9.8ppg by 1942m, reducing the overbalance at the top of the "Coarse Clastics" to 200psi.

After running logs and RFT's at 2021m, the well depth was extended to 2821m upon geologist's request. Since RFT results showed the pressure at the top of the "Coarse Clastics" to be less than anticipated, the mud weight was reduced further to 9.5ppg. In the extended hole section, a second core was cut from 2737.2m to 2754.6m. At 2821m, logs, RFT's and sidewall cores were run.

9-5/8" SUBSEA COMPLETION CASING AND WELL ABANDONMENT

Since an accumulation of oil was found in the Latrobe Formation, the well was to be left for a future subsea completion. Before the sands were cased off, a cement plug was set at 1600m to 1500m, just below the proposed casing shoe depth, to help ensure a better casing cement job. Since no hydrocarbons were found below 1450m, no other open hole cement plugs were set.

The 9-5/8" casing was run and cemented at a depth of 1485m. The casing string included two 10-3/4" casing joints just below the 10-3/4" casing hanger. The larger casing was used because the subsea safety valves run in a subsea completion will not fit easily inside 9-5/8" casing. The casing was cemented using a 9-5/8" subsea release plug set below a drillpipe stinger and wellhead running tool. The plug was bumped with 3000psi.

While preparing to run the seal assembly, a fatality occurred on the rig floor. Operations were shut down for 21-1/2 hours while the accident was investigated.

After the investigation, a Cameron 10-3/4" Weight Set seal assembly was set and tested to 5000psi. Open ended drillpipe was run and tagged the top of cement inside the casing at 1463m.

Cement Plug No. 2 was set inside the 9-5/8" casing from 160 to 95m using a 3-1/2" cement diverter tool, 3-1/2" tubing stinger, and 5" drillpipe. The BOP stack was then pulled. Divers measured the 10-3/4" seal assembly stack up inside the wellhead and cut the guidelines after the corrosion cap was set.

DEMOORING

After waiting 29 hours for weather, the rig was deballasted and all anchors were pulled by the Torrens Tide, Swan Tide and Lady Sally workboats. The rig departed the well location at 0445 hours on August 4, 1985 on tow by the Lady Sally to the East Halibut-1 location.

1848L/33-35

3. WHIPTAIL 1/1A CASING DATA

CSG O.D. in.	CSG WT. ppf	CSG GRADE	CSG CONN.	CSG LGTH mtrs.	CENTRALIZER POSITION.	SHOE DPTH mRKB	REMARKS
20	94	X-52	JV	12.58		180	Float Shoe Jnt.
20	94	X-52	٧L	85.87	Across Collars on First Five Jnts.		7 Jnts.
20	94	X-52	JV/CC	13.38			Crossover Jnt.
24	670		CC	10.96			Pile Jnt. Ass'y No. EP2
20	94	X-52	J۷	11.49		182	Float Shoe Jnt.
20	94	X-52	J۷	67.86	Across Collars on First Five Jnts.		7 Jnts.
20	129	X-52	JV/CC	12.36	THISCTITO CITE.		Crossover Jnt.
24	670		CC	11.10			Pile Jnt. Ass'y No. EP8
13-3/8	54.5	K-55	Butt.	12.43		782	Float Shoe Jnt.
13-3/8	54.5	K-55	Butt.	12.34			Float Collar Jnt.
13-3/8	54.5	K-55	Butt.	685.79	Across Collars on First Six Jnts.		59 Jnts.
13-3/8	54.5	K-55	Butt.	12.87	i ii oc oin oiles.		Hgr Jnt. Hgr No. EHW32. S/A No. ESW32.

WHIPTAIL 1/1A CASING DATA

CSG O.D. in.	CSG WT. ppf	CSG GRADE	CSG CONN.	CSG LGTH mtrs.	CENTRALIZER POSITION.	SHOE DPTH mRKB	REMARKS
9-5/8	47.0	N-80	Butt.	12.22	Middle of Jnt.	1,485	Float Shoe Jnt.
9-5/8	47.0	N-80	Butt.	11.79			Float Collar Jnt.
9-5/8	47.0	· N-80	Butt.	1,376.20	Across Collars On First 5 Jnts.		118 Jnts.
9-5/8	47.0	N-80	Butt.	1.86	11130 3 01103.		Pup Jnt.
10-3/4	51.0	N-80	Butt.	0.80			9-5/8"x10-3/4" Swedge
10-3/4	51.0	N-80	Butt.	11.60			1 Jnts.
10-3/4	51.0	N-80	Butt.	12.45			Hgr. Jnt. Hgr No. EHW 101. S/A NO. ESW 101.

4. WHIPTAIL 1/1A CEMENT DATA

CEMENT JOB Type	CEMENT TOP mRKB	CEMENT BTM mRKB	CEMENT ADDITIVES	CEMENT VOLUME sxs	CEMENT WEIGHT PPg	REMARKS
20" Csg	61	180	2.2% Gel w/ 173 Bbls Seawater	750	13.3	Lead Slurry. Divers confirm cmt returns.
20" Csg	-91	-163	42 Bbls Seawater	350	15.8	Tail Slurry. Cmt Inside Casing. Tagged TOC @ 91m.
20" Csg	60	99	2.2% Ge1 w/ 173 Bb1s Seawater	750	13.3	Lead Slurry. Divers confirm cmt returns.
20" Csg	99	182	42 Bbls Seawater	350	15.8	Tail Slurry. Bled back 1 Bbl. Float Held.
13-3/8" Csg	282	782	125 Bbls Seawater	1,050	15.8	Displace w/ 354 Bbls.Bump Plug w/ 1600 psi.
P&A Plug No. 1	1,500	1,600	32 Bbls Freshwater	269	15.8	Tagged @ 1482m. Dressed Off.
9-5/8" Csg	957	1,485	0.4% HR6L w/ 63 Bb1s FW	530	15.8	Displace w/ 335 Bbls. Bump Plug w/ 3000psi.Tagged TOC @ 1463m.
P&A Plug No. 2	95	160	9 Bbls Seawater	75	15.6	Set Inside 9-5/8" Csg.

Total: 4,124

WELL: WHIPTAIL 1A

5. SAMPLES, CONVENTIONAL CORES, SIDEWALL CORES

INTERVAL

TYPE

200.0 - 2820.0m Cuttings samples - 3 sets of washed and oven dried cuttings and 1 set of bagged and air dried cuttings.

Sampled from 200 - 1000m at 10m intervals, Sampled from 1000 - 1165m; 1175 - 2736m and

2755 - 2820m at 5m intervals.

200.0 - 2820.0m l set of unwashed canned samples for geochemistry,

collected at 15m intervals.

1050.0 - 2820.0m Washed and air dried canned samples every 30m (for

fission track analysis).

1165.4 - 1175.5m Core No.1, plastic sleeve, recovered 77% (7.8m)

2737.2 - 2754.6m Core No.2, recovered 56.3% (9.8m)

1120.0 - 2780.9m Sidewall Cores Run No.1 shot 60 recovered 55

1848L/28

WELL: WHIPTAIL-1A

6. WIRELINE LOGS AND SURVEYS

Type and		From	<u>To</u>					
		Suite 1						
BHC-GR	1:200 1:500		796.0	60.Om				
		Suite 2						
DLTE-MSFL-GR	1:200 1:500		2007.0	782.Om				
LDTC-CNTH-GR	1:200 1:500		2006.0	1100.Om				
BHC-GR	1:200 1:500		2007.0	782.Om				
RFT-HP (PRETEST AND RFT-GR (PRETEST AND								
		Suite 3						
DDBHC-GR	1:200 1:500		2815.5	1950.Om				
DLTE-MSFL-GR	1:200 1:500		2815.5	1950.Om				
LDTC-CNTH-GR	1:200 1:500		2809.5	1950.Om				
	RFT-HP (PRETEST & SAMPLE RECORD) RUNS 8-9 RFT-GR (PRETEST & SAMPLE RECORD) RUNS 8-9							
WST-GR (CHECKSHOT SU	RVEY) 18 LEVE	LS	2815.0	200.Om				
CST-GR	1:200		2781.0	1120.Om				

1848L/30

					RECOVER	RY (LITR				T-PACKARD ON PRESSURE		F-PACKARD	RE
TEST	SEAT	(METRES)	CHAMBER	OIL	COND.	GAS	FORMATION WATER	MUD FILTRATE	MPaa/g	Psia/g	MPaa/g	Psla/g	REMARKS
		<u>K.B.</u>	Litres	Litres	Litres	_m 3	Litres	Litres	(Note:	psia from HP psig from Sc	gauge hlumberger stra	ain gauge).	•
1	ı	1397.5	22.7 10.4	22.0 9.6	-	0.020		-	13.64	1979(g)	16.18	2347(g)	Valid pretest, sample taken
2	2	1380.2	22.7 10.4	16.3 -	-	0.006	-	5.25 -	13.52	1961 (g)	15.98	2317(g)	Valid pretest, sample taken Sample preserved
3	3	1285.5	22.7 10.4	-	-	0.018	21.5 9.7	-	12.56	1821 (g)	14.89	2159(g)	Valid pretest, sample taken
4	4	1295.0	22.7 10.4	-	_	-	21 . 5 9 . 75	-	12.64	1833(g)	14.98	2173(g)	Valid pretest, sample taken
5	5	1154.0	Sampling	g aband	oned	-	-	-	-	-	13.32	1932(g)	Tight
5	6	1154.0	Sampling	g aband	oned	-	-	-	-	-	13.32	1932(g)	Tight
5	7	1158.0	22.7 10.4	-	-	0.024 -	22.0 10.2	-	11.15	1617(g)	13,37	1939(g)	Valid pretest, sample taken
6	8	1497.5	Sampling	-		-	-	-	14.62	2121(g)	17.35	2517(g)	Seal failure
6	9	1497.0	Sampling	g aband	oned	-	-	-	- '	-	-	-	No seal
б	10	1497.0	22.7 10.4	-	-	-	20.5 9.0	-	14.63	2122(g)	17.35	2516(g)	Valid pretest, sample taken
7	11	1275.5	Sampling	-		-	-	-	-	-	14.73	2137(g)	Tight
7	12	1276.5	Sampling	~		-	-	-	-	-	14.73	2137(g)	Tight
7	13	1278.5	Sampling	g aband	oned	-	-	-	-	-	14.76	2141(g)	Tight
7	14	1454.0	Pretest						14.23	2064.3(a)	16.86	2445.9(a)	
7 7	15 16	1420.0 1403.5	Pretest Pretest						13.89 13.73	2014.3(a)	16.45	2385.7(a)	
7	16 17	1397.5	Pretest						13.73	1991.5(a) 1982.0(a)	16.26 16.19	2357.9(a) 2347.5(a)	
7	18	1392.0	Pretest						13.62	1902.0(a)	16.19	2337.6(a)	
7	19	1385.5	Pretest						13.58	1968.9(a)	16.04	2326.6(a)	
7	20	1380.0	Pretest						13.54	1963.2(a)	15.98	2317.4(a)	
7	21	1369.0	Pretest						13.37	1939.2(a)	15.85	2298.5(a)	
7	22	1352.5	Pretest						13.22	1916.8(a)	15.65	2270.3(a)	

		DEPTH			RECOVER	RY (LITR	ES) FORMATION	MUD		T-PACKARD ON PRESSURE		T-PACKARD ATIC PRESSU	RE
TEST	SEAT	(METRES)	CHAMBER	OIL	COND.	GAS	WATER	FILTRATE	MPaa	Psta	MPaa	Psia	REMARKS
		K.B.	Litres	Litres	Litres	m ³	Litres	Litres	•	sia from HP gau sig from Schlum	-	n gauge)	
7	23	1331.0	Pretest						13.01	1886.8(a)	15.40	2234,2(a)	Valid
7	24	1363.5	22.7 10.4	<u>-</u>	0.014	-	22.0 10.0	-	13.27	1924.(g)	15.71	2279(g)	Valid pretest, sample taken
8	25	2664.5	Sampling	- Ahanc	doned	_	10.0		26.17	3706/ ~)	20.01	47707-1	Sample taken.
8	26	2665.0	Sampling						20.17	3796(g)	29.91 29.82	4338(g) 4325(g)	Tight
8	27	2666.8	Sampling						26.09	3784(g)	29.82	4325(g) 4325(g)	Tight Tight
8	28	2663.7	Sampling						_	-	29.79	4320(g)	Tight
8	29	2665.0	Sampling						_		29.82	4325(g)	Tight
8	30	2650.0	Sampling	Aband	loned				-	-	29.65	4301 (g)	Tight
8	31	2649.5	Sampling	Abanc	loned				25.88	3754.0	29.65	4300(g)	Tight
8	32	2648.5	Sampling	Aband	loned				25.86	3750.0	29.61	4295 (g)	Tight
8	33	2651.0	45.4		-	0.023	-	20.0	25.89	3755.0	29.66	4302(g)	Tight - Composite sample of run 8
9	34	1497.0	Pretest						14.65	2124.3	16.82	2439,4(a)	
9	35	1467.0	Pretest						14.35	2081.9	16.47	2389.3(a)	Valid
9	36	1436.0	Pretest						14.05	2038.3	16.12	2337.5(a)	Valid
9	37	1407.0	Pretest						13.76	1996.0	15.78	2288,5(a)	Valid
9	38	1380.0	Pretest						13.53	1962.5	15.53	2252.8(a)	Valid
9	39	2665.0	Sampling						-	-	29.93	4341.0(a)	Tight
9	40	2665.0	Sampling	Aband	loned				-	-	29.95	4344.0(a)	Tight
9	41	2664.5	45.4	-	-	0.017	-	7.3	26.21	3801(a)	29.94	4342.0(a)	Valid pretest Sample taken
			10.4	-	-	tr	-	3.0					Sample taken

8. TEMPERATURE RECORD - WHIPTAIL-1A

LOGGING RUN	THERMOMETER DEPTH (m)	MAX. RECORDED TEMPERATURE (C°)	CIRCULATION TIME (t _k) (hours)	TIME AFTER CIRCULATION STOPPED (t)	HORNER TEMPERATURE (C°)	GEOTHERMAL GRADIENT (Cº/km)
Suite 1						
BHC-GR	796.0	44.4	1.0	5.0		
Suite 2						
DLTE-MSFL-LDTC-CNTH-GR (Combination Tool)	2007.0	72.2	1.0	5.0	86.0	38.81
BHC-GR	2007.0	78.8	1.0	10.0		
RFT-GR (Pretest and Sample Record)	1497.5	70.5	1.0	35 . 5		
Suite 3						
DLTE-MSFL-LDTC-CNTH-GR (Combination Tool)	2815.5	82.0	1.0	6.37	144.2	48.64
DDBHC-GR	2815.5	113.0	1.0	13.18		
RFT-GR (Pretest and sample	e) 2665 . 0	91.0	1.0	25.82		
CST-GR	2781.0	113.0	1.0	36.67		

FIGURES

LOCALITY MAP

WHIPTAIL - 1A

SCALE 1:250 000




FIGURE 1




FIGURE 2

WHIPTAIL 1A WELLBORE SCHEMATIC





FIGURE 3

WHIPTAIL I ABANDONMENT SCHEMATIC



PRIMARY CEMENT
ALL DEPTHS ARE MEASURED FROM RKB

FIGURE 4A

WHIPTAIL 1A ABANDONMENT SCHEMATIC




FIGURE 4B

FIGURE 5A 88 WHIPTAIL-1A 87 HORNER TEMPERATURE PLOT Horner Temperature = 86.0°C 86 WIRELINE LOGGING SUITE 2 tk = circulation time 1.0 hours 85 Δt = time since circulation Geothermal Gradient = 0.0388°C/m = 38.81°C/km 84 83 KB height = 21m Sea Bottom Temperature = 10°C 82 Water Depth = 39m 81 80 79 78 77 76 75 74 73 72 1.4 1.2 1.1 1.0 1.9 1.8 1.7 1.6 1.5 1:3 $tk+\Delta t$

FIGURE 5B WHIPTAIL-1A 142 HORNER TEMPERATURE PLOT Horner Temperature = 144.2°C 138 WIRELINE LOGGING SUITE 3 tk = circulation time 1.0 hours 134 Δt = time since circulation Geothermal Gradient = 0.0486^oC/m = 48.64^oC/km 130 126 KB height = 21m Sea Bottom Temperature = 10°C 122 Water Depth = 39m 118 114 110 106 102 98 94 90 86 82 1.9 1.4 1.1 1.0 1.8 1.7 1.6 1.5 1.3 1.2

 $\frac{tk+\Delta t}{\Delta t}$

APPENDIX 1

APPENDIX 1

Lithological Descriptions

WHIPTAIL-1A

Lithology Descriptions

<u>Depth</u>	<u>%</u>	<u>Descriptions</u>
200-210m	100	CALCARENITE: White to light grey (fossiliferous limestone) dominantly fossil fragments e.g. coral, gastropods, fragments of brachiopods (larger cement fragments present).
210-220m	100	CALCARENITE: [fossiliferous limestone] as above.
220-230m	100	CALCARENITE: As above.
230-240m	100	CALCARENITE: Dominantly fossil fragments including coral, gastropods, brachiopods [fossiliferous limestone], clean.
240-250m	100	CALCARENITE: As above.
250-260m	100	CALCARENITE: As above.
260-270m	100	CALCARENITE: As above, or fossiliferous limestone, fine to medium grained aggregates, medium to hard.
270-280m	100	CALCARENITE: As above.
280-290m	100	CALCARENITE: As above.
290 - 300m	100	CALCARENITE: Dominantly fossiliferous fragments.
300 - 310m	100	CALCARENITE: As above, i.e. light grey, white to buff, hard to medium hard, fine to medium grained, very abundant fossils, clean. Trace pyrite, trace glauconite.
310 - 320m	100	CALCARENITE: Dominantly fossiliferous fragments, some aggregates, medium hard, light grey to white, medium grained, trace pyrite and glauconite.
320-330m	100	CALCARENITE: As above.
330-340m	100	CALCARENITE: As above.
340 - 350m	100	CALCARENITE: As above.
350-360m	100	CALCARENITE: Bright white, occasionally very light grey, dominantly white, very fossiliferous, very firm to brittle, predominantly fossil fragments, of coral, brachiopods, forams and gastropods.
360-370m	100	CALCARENITE: As above.
370-380m	50 50	CALCARENITE: As above. SANDSTONE: Translucent, clear, white, yellow, well rounded grains, subrounded, medium to coarse grains, poor to moderately sorted, no matrix detectable, coarse quartz grains, occasional fine grains.

		24/
	•	- 2 -
380-390m	50 50	SANDSTONE: As above. CALCARENITE: As above, light grey to white.
390-400m	70 30	SANDSTONE: Loose quartz grains, translucent, clear, white, yellow occasionally light blue, very well rounded, occasionally sub rounded, frosted, medium to fine grained, occasional coarse grains, moderately sorted. CALCARENITE: As above.
400-410m	70 · 30	SANDSTONE: Loose quartz grains, as above. CALCARENITE: As above.
410-420m	100	SANDSTONE: Loose quartz grains, fine to medium grained, moderately well sorted, subrounded.
420-430m	80 20	SANDSTONE: Loose quartz, as above. CALCARENITE: As above. Shell fragments.
430-440m	40	SANDSTONE: Loose quartz, as above, medium to coarse grained, occasionally fine grained, well rounded to rounded, frosted as above. CALCARENITE: As above.
440 – 450m	80 20	CALCARENITE: White, light grey, very fossiliferous, firm to brittle, shell fragments, coral fragments, bryozoans. SANDSTONE: Loose quartz, medium to coarse grains, subrounded to subangular, poor to moderately sorted, translucent, yellow, clear, white.
450-460m	100	CALCARENITE: Light grey, white, very fossiliferous, firm to brittle, coral fragments, shell fragments, bryozoans, gastropods, very fossiliferous.
460-470m	100	CALCARENITE: As above.
470-480m	100	CALCARENITE: As above.
480-490m	100	CALCARENITE: As above.
490 - 500m	100	CALCARENITE: As above. Predominantly white, occasionally light grey, very fossiliferous.
500-510m	100	CALCARENITE: As above.
510 - 520m	80 20	CALCARENITE: As above. SANDSTONE: Loose quartz grains, medium to coarse grained, translucent, opaque, white, smokey to frosted, well rounded to rounded, moderately to poorly sorted.
520 – 530m	100	SANDSTONE: Loose quartz grains, translucent, white, frosted, well rounded to rounded, moderately sorted, very clean, fossiliferous fragments, shell/coral fragments, bryozoans, subrounded to subangular in parts.
530 - 540m	100	CALCARENITE: As above. Loose quartz common.
540550m	100	CALCARENITE: 100% loose quartz grains.

550-560m	100	CALCARENITE: 90% loose quartz grains, translucent, white, clear, frosted, well rounded to rounded to occasionally subangular, moderately sorted, matrix not visible, very fossiliferous, shell/coral fragments, bryozoans, as above.
560 - 570m	100	CALCARENITE AGGREGATES: Very fine quartz grains, fossiliferous, white, light grey-20% loose quartz grains.
570-580m	100	CALCARENITE: As above, 10% loose quartz aggregates.
580-590m	90	CALCARENITE: White to light grey, very fine to fine to medium grained quartz, very occasional loose quartz grains, subrounded to subangular, clear white translucent quartz aggregates, very fossiliferous, coral, shell fragments common, bryozoa, forams. CALCISILTITE: Light grey to grey,
	10	fossiliferous, grading to Calcarenitic in parts, silty matrix.
590-600m	90 10	CALCARENITE: As above. Aggregates firm to hard. CALCISILTITE: As above.
600 - 610m	100	CALCARENITE: As above. Trace glauconite.
610-620m	80 20	CALCARENITE: As above, trace glauconite. CALCISILTITE: Light grey, grey, firm to hard, brittle, silty, argillaceous and calcitic matrix, coral/shell fragments, forams, bryozoans. Trace Calcilutite, grey, firm to moderately hard, silty.
620 - 630m	80 20	CALCARENITE: As above. CALCISILTITE: As above, occasional pyrite. Trace Calcilutite.
630 - 640m	70 30	CALCARENITE: As above. CALCISILTITE: As above, occasional pyrite.
640-650m	70 30	CALCARENITE: As above CALCISILTITE: As above.
650 – 660m	50 50	CALCARENITE: As above CALCISILTITE: Light grey to grey, blocky, firm to moderately hard, silty argillaceous calcitic matrix grading to Calcilutite in parts, soft to firm, glauconitic. Fossiliferous fragments, coral, bryozoa, forams.
660-670m	40 60	CALCARENITE: As above CALCISILTITE: As above, commonly grey to occasionally light grey, soft, sticky, micro-micaceous, shell fragments.
670-680m	30 70	CALCARENITE: As above CALCISILTITE: As above.
680 - 69 0 m	80 20	CALCARENITE: As above predominantly white. CALCISILTITE: As above.

690-700m	80 20	CALCARENITE: As above. CALCISILTITE: As above.
700-710m	20	CALCARENITE: White to light grey, very fine to fine grained quartz, moderately sorted, fossiliferous, shell fragments and bryozoans, occasionally medium to coarse grained quartz, well rounded, calcitic matrix. CALCISILTITE: Grey to light grey, occasionally fossiliferous fragments, blocky, firm to very hard, siliceous in parts, pyritic in parts, trace dolomite.
710-720m	70 30	CALCARENITE: As above CALCISILTITE/CALCAREOUS SILTSTONE: grey to light grey to grey-brown, soft to firm to very hard in parts, predominantly firm, blocky, occasionally very fine to fine quartz grains, pyritic inclusions, argillaceous and predominantly calcite matrix.
720-730m	50	CALCAREOUS SILTSTONE: Grey to light grey to grey-brown, soft to firm to hard, blocky with occasional fine grained quartz, pyritic in part with predominantly calcite matrix, argillaceous in part. CALCARENITE: As above.
730-740m	60 40	CALCISILTITE: Soft to moderately firm, grey to light grey to brown, blocky, occasional quartz inclusions, occasional pyrite, calcite matrix, argillaceous in part. CALCISILTITE: Light grey to grey, moderately hard to hard, moderate sorting. Occasional fossil fragments including corals, shell fragments, gastropods, bryozoa.
740-750m	50 50	CALCARENITE: As above. CALCISILTITE: As above. Occasional fossils and pyrite.
750 –7 60m	60 40	CALCARENITE: Soft to moderately firm, some quartz grains, calcareous cement, fine to medium grained. CALCISILTITE: Grey to light brown, soft to moderately firm, blocky, calcite matrix. Occasionally pyritic, fossils and calcite crystals.
760 - 770m	70 30	CALCARENITE: White, light grey, medium to coarse grains, firm to moderately hard, friable in parts. CALCISILTITE: Grey to grey brown, firm, friable, blocky, occasional fossils.
770-780m	60 40	CALCARENITE: White to grey, fine to medium grained, soft to firm, some moderately hard, friable in parts. CALCISILTITE: Grey to grey-brown, soft to firm, blocky. Occasional of fossils replaced by pyrite.
780-790m	60 40	CALCARENITE: As above. CALCISILTITE: As above.
790-800m	70 30	CALCARENITE: As above CALCISILTITE: As above.

800-810m	70 30	CALCARENITE: Light to medium grey, firm, scattered carbonaceous siltstone spread evenly throughout, firm, blocky, occasionally light grey, coarse. Broken limestone shell fragments in a light calcareous matrix, common buff to white bryozoa with distinct apertures and fenestrae, good sorting. CALCISILTITE: Grey, firm, blocky, calcareous matrix, very clear.
810-820m	50 50	CALCARENITE: As above. CALCISILTITE: As above. Trace pyrite, crystalline limestone in parts.
820 - 830m	80 20	CALCISILTITE: Light grey, argillaceous, soft to occasionally firm, blocky to poorly indurated, very clean. CALCARENITE: As above.
830-840m	90 10	CALCISILTITE: As above (soft), argillaceous. CALCARENITE: As above.
840-850m	90 10	CALCISILTITE: Light grey-green to grey, soft to occasionally firm, argillaceous in parts, very calcareous, trace fossils, trace pyrite. CALCARENITE: Light grey to white, very fine grained sandy, very calcareous and argillaceous, friable to soft.
850-860m	70 30	CALCISILTITE: As above CALCARENITE: As above.
860-870m	100	CALCISILTITE: As above.
870-880m	100	CALCISILTITE: Light grey to light grey-green, soft to occasionally friable, poorly indurated to blocky, argillaceous, fossiliferous.
880-890m	100	CALCISILTITE: As above.
890-900m	100	CALCISILTITE: As above.
900-910m	100	CALCISILTITE: As above.
910 - 920m	100	CALCISILTITE: As above.
920 - 930m	100	CALCISILTITE: As above.
930 - 940m	100	CALCISILTITE: As above.
940-950m	100	CALCISILTITE: As above.
950-960m	100	CALCISILTITE: As above. Light grey to grey-green, soft to firm, occasionally friable, poorly indurated, blocky, argillaceous, fossiliferous, carbonaceous inclusions in parts.
960-970m	100	CALCISILTITE: Light grey to green-grey, soft to firm, friable, argillaceous, occasional fossils.
970-980m	100	CALCISILTITE: As above.
980 - 990m	100	CALCISILTITE: As above.

	990-1000m	100	CALCISILTITE: As above.
· •	1000-1005m	100	CALCISILTITE: As above
	1005 - 1010m	100	CALCISILTITE: Grey to light grey to grey green, blocky, soft, occasionally firm, argillaceous cement, subfissile in parts, fossiliferous in parts, poorly indurated grading to Calcilutite.
	1010-1015m	100	CALCISILTITE: As above.
•	1015-1020m	100	CALCISILTITE: As above.
	1020 - 1025m	100	CALCISILTITE: As above. Grading to Calcilutite in parts.
	1025-1030m	100	CALCISILTITE: As above.
i	1030-1035m	100	CALCISILTITE: As above.
	1035-1040m	100	CALCISILTITE: Grey to light grey to grey-green, occasionally grey-brown, blocky, soft to firm, argillaceous matrix, very calcareous, sub fissile in parts, fossiliferous in parts, poorly indurated, grading to Calcilutite in parts.
	1040-1045m	100	CALCISILTITE: As above.
1	1045-1050m	100	CALCISILTITE: As above.
	1050 - 1055m	100	CALCISILTITE: Grey to occasionally light grey to grey brown, blocky, soft to firm, argillaceous matrix, very calcareous, fossiliferous in parts, bryozoa, moderately indurated, grading to Calcilutite.
	1055-1060m	100	CALCISILTITE: As above, grading to Calcilutite.
	1060-1065m	100	CALCISILTITE/CALCARENITE: As above.
	1065-1070m	100	CALCISILTITE: As above.
	1070-1075m	100	CALCARENITE/CALCISILTITE: Becoming increasingly argillaceous, otherwise as above.
	1075 - 1080m	100	CALCISILTITE: As above.
	1080-1085m	100	CALCISILTITE: As above.
	1085 -1 090m	100	CALCISILTITE: As above.
	1090 - 1095m	100	CALCISILTITE: Pale brown to light blue grey, predominantly argillaceous with a calcitic matrix, soft, water sensitive in parts, blocky, rare fossiliferous fragments, scattered pyrite.
	1095 - 1100m	100	CALCISILTITE: As above.
	1100 - 1105m	100	CALCISILTITE: As above.
	1105-1110m	100	CALCISILTITE: Trace dark green coarse angular glauconite pellets, otherwise as above.

1110-1115m	100	CALCISILTITE: As above.
1115 - 1120m	100	CALCISILTITE: Glauconite becoming more abundant, otherwise as above.
1120-1125m	100	CALCISILTITE: As above.
1125 - 1130m	100	CALCISILTITE: Pale brown to pale blue grey, argillaceous to silica matrix in a predominantly calcareous cement, water sensitive in part, trace fossil fragments, occasional pyrite, common very coarse to granular, subrounded glauconite pellets.
1130-1135m	100	CALCISILTITE: As above.
1135 - 1140m	100	CALCISILTITE: Becoming increasingly fossiliferous: bryozoa, forams.
1140 - 1145m	100	CALCISILTITE: Commonly beige angular, granular sized, hard cryptocrystalline limestone clasts, less glauconite, occasional fossils, becoming increasingly siliceous.
1145 - 1150m	100	CALCISILTITE: Scattered glauconite pellets, slightly more argillaceous, otherwise as above.
1150-1155m	100	CALCISILTITE: Trace clear loose quartz grains - otherwise as above.
1155-1160m	70	CALCISILTITE: Grading to argillaceous siltstone, no shows.
	30	SANDSTONE: Clear, loose, coarse grained, subangular to angular quartz, occasionally well cemented medium grained quartz aggregates, fair sorting, good porosity. No fluorescence or cut, common glauconite.
1160 - 1165m	80 20	SANDSTONE: As above. SILTSTONE: Brown, argillaceous to calcareous matrix, water sensitive in parts.
Core #1 1165.4-1175.5m		See Core Description No. 1
1175 - 1180m	100	SANDSTONE: Clear to translucent, very clean, fine to medium to coarse grains, predominantly medium to coarse grains, poorly sorted, sub angular to angular. No fluorescence, good porosity, no shows.
1180 - 1185m	100	SANDSTONE: As above. No fluorescence.
1185 - 1190m	100	SANDSTONE: As above. 5% dull to bright yellow mineral fluorescence.
1190 - 1195m	100	SANDSTONE: As above 10% yellow mineral fluorescence.
1195 - 1200m	100	SANDSTONE: Clear to translucent, white, medium to coarse grained, occasionally fine grained, subangular to subrounded, moderate to poorly sorted, 10% yellow mineral fluorescence, good porosity, no shows.

		_ 0
1200-1205m	60 40	SANDSTONE: As above. 10% dull yellow occasionally bright mineral fluorescence. SILTSTONE: Dark grey-brown to black-brown, firm to hard, predominantly hard, brittle, very carbonaceous grading to coal in parts.
1205-1210m	70 30	SILTSTONE: Dark brown, black brown, grey, blocky to occasionally subfissile, firm to hard, predominantly hard, brittle, very carbonaceous, grading to coal in parts. SANDSTONE: As above. 5% dull mineral fluorescence.
1210-1215m	70 30	SILTSTONE: As above. SANDSTONE: As above.
1215-1220m	60 40	SILTSTONE: 30% carbonaceous siltstone, as above. 30% light grey to grey, argillaceous, blocky, carbonaceous flecks, soft to firm to moderately hard, predominantly firm to moderately hard, trace pyrite. SANDSTONE: As above.
1220-1225m	70 30	SILTSTONE: As above. SANDSTONE: As above.
1225 - 1230m	60	SANDSTONE: Bimodal, white, clear, loose to frosted coarse to very coarse subrounded quartz grains grading to mainly medium grained, good porosity, no shows.
e e e e e e e e e e e e e e e e e e e	40	SILTSTONE: Brown, grey, argillaceous, to carbonaceous, firm to hard, blocky, pyrite common.
1230-1235m	100	SANDSTONE: As above.
1235-1240m	100	SANDSTONE: As above.
1240 - 1245m	100	SANDSTONE: Bimodal, white, clear, loose frosted, coarse to very coarse subangular to angular quartz grains, very immature, fine to medium grained quartz forming coarse aggregates, slightly calcareous matrix, no shows.
1245 - 1250m	50 50	SANDSTONE: As above. SILTSTONE: As above.
1250 - 1255m	90 10	SANDSTONE: As above. SILTSTONE: As above.
1255 - 1260m	100	SANDSTONE: As above.
1260-1265m	100	SANDSTONE: As above.
1265 - 1270m	100	SANDSTONE: As above.
1270-1275m	100	SANDSTONE: As above.
1275-1280m	100	SANDSTONE: White, clear, frosted, loose, coarse grained angular quartz fragments, well faceted, welded quartz aggregates, occasionally very coarse to granular sized angular smokey quartz fragments.

1280-1285m	80 20	SANDSTONE: As above. SILTSTONE: Dark grey brown, very carbonaceous, slightly argillaceous, blocky, firm.
1285-1290m	50 50	SANDSTONE: As above. SILTSTONE: As above.
1290-1295m	70 30	SANDSTONE: As above. SILTSTONE: As above.
1295 - 1300m	100	SANDSTONE: As above.
1300-1305m	100	SILTSTONE: As above.
1305 - 1310m	70 30	SANDSTONE: As above. SILTSTONE: As above.
1310 - 1315m	80 20	SANDSTONE: As above SILTSTONE: As above
1315 - 1320m	70 30	SANDSTONE: As above. SILTSTONE: Very carbonaceous, grading to a dirty coal, otherwise as above.
1320-1325m	70 30	SANDSTONE: As above. SILTSTONE: As above.
1325 - 1330m	100	SILTSTONE: Clear to frosted, clean, coarse to very coarse grained, angular loose quartz, well faceted, immature, excellent inferred porosity, no shows.
1330 - 1335m	100	SANDSTONE: As above.
1335-1340m	100	SANDSTONE: As above.
1340-1345m	100	SANDSTONE: As above.
1345-1350m	100	SANDSTONE: As above.
1350 - 1355m	100	SANDSTONE: As above.
1355-1360m	100	SANDSTONE: As above.
1360 - 1365m	60 40	SANDSTONE: As above. SILTSTONE: As above.
1365 - 1370m	100	SANDSTONE: As above.
1370 – 1375m	70 30 Trace	COAL: Black, brittle - friable, vitreous. SANDSTONE: clear to translucent, coarse to very coarse grains, loose, no matrix, quartz, subangular to angular grains, good visual porosity, no shows. SILTSTONE: Dark brown, friable, carbonaceous, fissile to blocky.
1375-1380m	60 30 10	SANDSTONE: As above. COAL: As above. SILTSTONE: As above (trace pyrite).
1380-1385m	60 20 20	SANDSTONE: As above. SILTSTONE: As above. COAL: As above.

1385 - 1390m	70 20 10	SANDSTONE: As above, more than 10% calcite mineral fluorescence. SILTSTONE: As above. COAL: As above.
1390 - 1395m	70 20	SANDSTONE: 10% calcite mineral fluorescence; otherwise as above. SILTSTONE: As above
	10	COAL: As above.
1395 - 1400m	30 50	SANDSTONE: As above. SILTSTONE: Very carbonaceous, blocky, grading in part to a dirty coal.
	20	COAL: As above.
1400-1405m	30 50 20	SANDSTONE: As above. SILTSTONE: As above. COAL: As above.
1405 -1 410m	80	SANDSTONE: Clear to translucent, coarse to very coarse grained quartz, loose, no matrix, well sorted subangular to angular grains, good visual porosity. Less than 10% dull white fluorescence with very slow diffuse milky white cut.
	10	SILTSTONE: Very dark brown, grading to coal,
	10	friable, very carbonaceous, arenaceous in part. COAL: Black, brittle to friable, grades to carbonaceous siltstone.
1410-1415m	100	SANDSTONE: As above.
1415-1420m	70	SANDSTONE: As above less than 5% dull white fluorescence with very slow diffuse milky white cut.
	20 10	COAL: As above, trace pyrite. SILTSTONE: As above.
1420 - 1425m	80 20	SANDSTONE: As above, no shows. COAL: As above.
1425-1430m	70 10 20	SANDSTONE: As above. SILTSTONE: As above. COAL: As above.
1430-1435m	100 Trace Trace	SANDSTONE: As above. SILTSTONE: As above. COAL: As above.
1435 - 1440m	50 40	SANDSTONE: As above. SILTSTONE: Dark brown to light brown, carbonaceous, argillaceous, gummy.
	10	COAL: As above.
1440-1445m	100	SANDSTONE: As above.
1445 - 1450m	80 10 10	COAL: As above. SANDSTONE: As above. SILTSTONE: As above.
1450-1455m	50 30 20	SANDSTONE: As above. COAL: As above. SILTSTONE: As above

1455 -1 460m	100	SANDSTONE: As above.
1460-1465m	100	SANDSTONE: Predominantly white, clear to occasionally pale yellow, clean, loose, coarse to very coarse grained, angular quartz grains without any matrix; trace very fine to fine grained subangular to subrounded quartz aggregates in a dominantly silica matrix; good sorting, good inferred porosity. No shows.
1465-1470m	100	SANDSTONE: As above.
1470-1475m	100	SANDSTONE: As above.
1475-1480m	100	SANDSTONE: As above.
1480-1485m	100	SANDSTONE: As above.
1485 - 1490m	100	SANDSTONE: As above.
1490 - 1495m	90 10	SANDSTONE: As above, trace pyrite, no shows. COAL: As above.
1495 - 1500m	100	SANDSTONE: As above, no fluorescence, no shows. Trace coal and siltstone.
1500 -1 505m	100	SANDSTONE: As above.
1505-1510m	100	SANDSTONE: Clear to white, predominantly quartz, medium to coarse grained sandstone, subangular to subrounded, very good sorting, trace coal and pyrite and siltstone. No shows.
1510 - 1515m	90 10	SANDSTONE: As above. SILTSTONE: Dark grey to brown, carbonaceous, argillaceous, firm to hard, trace pyrite, grading to coal in parts.
1515-1520m	100	SANDSTONE: As above.
1520 - 1525m	90 10	SANDSTONE: As above. SILTSTONE: As above.
1525 - 1530m	100	SANDSTONE: Type 1: 50% As above. Type 2: 50% white, clear, translucent, medium to coarse grained, subangular to subrounded, good sorting, white clayey matrix (soft sticky) traces of pyrite and coal.
1530 - 1535m	90 10	SANDSTONE: As above Type 1: 40% Type 2: 60%. SILTSTONE: As above
1535 - 1540m	100	SANDSTONE: Type 1: 60%. Type 2: 40%. No shows. No fluorescence.
1540-1545m	100	SANDSTONE: Translucent, clear, white, coarse to very coarse grained to occasionally medium grained, very angular to angular, frosted, poor to moderately sorted, trace pyrite, no shows. Also 30% in white clay matrix, sticky. Trace coal/siltstone.

	1545-1550m	100	SANDSTONE: Translucent to white, coarse grained, subangular to subrounded, moderately sorted, no matrix. Minor coal, siltstone and white clay matrix, no shows.
	1550 – 1555m	100	SANDSTONE: Translucent clear to white, coarse grained, subangular to subrounded in part. Good sorting, no cement or matrix, traces of pyrite, coal, traces of white argillaceous clay. No shows.
	1555-1560m	100	SANDSTONE: As above, increase in pyrite.
	1560 - 1565m	100	SANDSTONE: As above, with an increase in the amount of pyrite compared to previous sample.
	1565 - 1570m	100	SANDSTONE: As above, increase in coal 5%.
	1570-1575m	100	SANDSTONE: Translucent, clear, occasionally white, frosted, angular to subangular quartz, coarse to very coarse grained, granular in parts. No shows. Moderate to well sorted, no matrix, pyrite increasing to 5-10%, trace coal.
	1575-1580m	100	SANDSTONE: As above.
	1580-1585m	100	SANDSTONE: As above.
	1585 - 1590m	100	SANDSTONE: As above.
	1590-1595m	100	SANDSTONE: As above
	1595-1600m	100	SANDSTONE: As above
	1600-1605m	100	SANDSTONE: Trace dull white yellow calcite mineral fluorescence, otherwise as above.
	1605 - 1610m	100	SANDSTONE: 10% dull yellow gold mineral fluorescence.
	1610-1615m	100	SANDSTONE: As above.
	1615-1620m	100	SANDSTONE: As above.
	1620-1625m	100	SANDSTONE: As above.
	1625-1630m	100	SANDSTONE: As above.
-	1630-1635m	100	SANDSTONE: As above.
	1635 - 1640m	100	SANDSTONE: No mineral fluorescence.
	1640 - 1645m	100	SANDSTONE: As above.
	1645 - 1650m	100	SANDSTONE: As above.
	1650 - 1655m	100	SANDSTONE: As above.
	1655 - 1660m	100	SANDSTONE: White, clear, frosted, coarse to very coarse grained, very angular to angular, loose quartz grains, no matrix, 10% bright white yellow mineral fluorescence.
	1660-1665m	100	SANDSTONE: As above.

1665-1670m	100	SANDSTONE: As above.
1670-1675m	100	SANDSTONE: Clean translucent, coarse to very coarse, loose quartz, no matrix, subangular to angular grains, well sorted, no shows. 5% mineral fluorescence.
	Trace	COAL: Grades to very carbonaceous siltstone, black, blocky, friable, brittle.
1675-1680m	100 Trace	SANDSTONE: As above. SILTSTONE: Dark brown to light grey, carbonaceous flecks in part, otherwise very carbonaceous, friable to soft, argillaceous.
1680 - 1685m	60 10 30	SANDSTONE: As above. SILTSTONE: As above. COAL: As above.
1685-1690m	60 20 20	SANDSTONE: As above. SILTSTONE: As above. COAL: As above.
1690 - 1695m	100	SANDSTONE: As above.
1695 - 1700m	90 10	SANDSTONE: As above. COAL: As above.
1700-1705m	90 10	SANDSTONE: As above. COAL: As above.
1705-1710m	100 Trace	SANDSTONE: As above SILTSTONE: As above.
1710-1715m	100	SANDSTONE: As above.
ļ715 - 1720m	100	SANDSTONE: Clear to translucent, coarse to very coarse grained, well sorted, loose quartz, no matrix, subangular to angular grains, no shows, trace pyrite.
1720 - 1725m	100	SANDSTONE: As above.
1725-1730m	100	SANDSTONE: As above.
1730-1735m	100	SANDSTONE: As above.
1735-1740m	100	SANDSTONE: As above.
1740-1745m	100	SANDSTONE: As above
1745-1750m	100	SANDSTONE: As above.
1750-1755m	100	SANDSTONE: As above.
1755-1760m	100	SANDSTONE: As above.
1760-1765m	100	SANDSTONE: As above.
1765-1770m	100	SANDSTONE: As above.
1770 - 1775m	100	SANDSTONE: Clear to translucent, loose quartz, well sorted, coarse to very coarse grains, subrounded to subangular (dominantly angular) no matrix or cement, trace pyrite aggregates with quartz.

Ì	1775-1780m	100	SANDSTONE: As above.
1	1780-1785m	100	SANDSTONE: As above.
	1785 - 1790m	100	SANDSTONE: Clear, clean, frosted, loose, medium to coarse grained, subangular to subrounded quartz grains — no matrix, good sorting, good porosity, trace pyrite. No shows.
	1790-1795m	100	SANDSTONE: As above.
	1795-1800m	100	SANDSTONE: As above.
ı	1800-1805m	100	SANDSTONE: As above.
	1805-1810m	100	SANDSTONE: As above.
	1810-1815m	100	SANDSTONE: As above.
	1815-1820m	100	SANDSTONE: As above.
	1820-1825m	1.00	SANDSTONE: As above.
· •	1825-1830m	100	SANDSTONE: As above.
	1830 - 1835m	100	SANDSTONE: As above.
: I	1835 -1 840m	100	SANDSTONE: As above.
	1840-1845m	100	SANDSTONE: As above
	1845 -1 850m	100	SANDSTONE: As above.
	1850-1855m	100	SANDSTONE: As above.
	1855 - 1860m	100	SANDSTONE: As above.
	1860-186 <i>5</i> m	100	SANDSTONE: Clear to translucent-white, loose quartz grains, subangular to angular, well sorted, no matrix, good inferred porosity, no shows. Trace pyrite.
	1865-1870m	100	SANDSTONE: As above.
	1870-1875m	100	SANDSTONE: As above.
	1875-1880m	100	SANDSTONE: As above.
	1880-1885m	100	SANDSTONE: As above.
	1885-1890m	100	SANDSTONE: Clear to translucent white, loose quartz grains, moderately well sorted, no matrix, subangular to angular, good visual porosity, no shows, common pyrite.
	1890 - 189 <i>5</i> m	100 Trace	SANDSTONE: Type 1: As above. Type 2: translucent white, medium to fine grained, argillaceous matrix, friable, subangular to angular, moderately sorted, no shows, moderate to poor visual porosity, Common pyrite. SILTSTONE: Light grey to dark brown,
			argillaceous, arenaceous, carbonaceous.
	1895-1900m	100	SANDSTONE: As above.

	1900-190 <i>5</i> m	100	SANDSTONE: As above.
	1905 - 1910m	100	SANDSTONE: (one type only). Clear - translucent, trace white, coarse to very coarse grained, loose quartz, no matrix, subangular to angular, moderate to well sorted, no show, good visual porosity. Trace pyrite.
•	1910 - 1915m	100	SANDSTONE: Clear to translucent to frosted, coarse to very coarse grained, loose quartz, no matrix, subangular to angular grains, moderately well sorted, good inferred porosity, no shows, common pyrite.
	1915-1920m	100	SANDSTONE: As above.
	1920-1925m	100	SANDSTONE: As above.
	1925-1930m	100	SANDSTONE: As above.
	1930 - 1935m	100	SANDSTONE: As above
	1935 - 1940m	100	SANDSTONE: As above.
	1940-194 <i>5</i> m	100	SANDSTONE: As above.
	1945 - 1950m	100	SANDSTONE: As above.
	1950-1955m	100	SANDSTONE: As above.
	1955 -1 960m	100	SANDSTONE: As above.
	1960-1965m	100	SANDSTUNE: As above.
	1965 - 1970m	100	SANDSTONE: Clear to translucent, frosted, white, coarse to very coarse grains, occasionally medium grained, moderate to well sorted, loose quartz, subangular to angular grains, good visual porosity, no shows, common pyrite. Trace fine to medium grained subangular to subrounded quartz aggregates in a silica matrix.
	1970-1975m	100	SANDSTONE: As above.
	1975 - 1980m	100	SANDSTONE: As above.
	1980 - 1985m	100	SANDSTONE: Clear, translucent to frosted, predominantly medium to occasionally fine grained, subangular, loose quartz, no matrix, trace medium grained subangular quartz aggregates in a dominately silica matrix, excellent sorting, good inferred porosity, no shows, trace pyrite.
	1985-1990m	100 Trace	SANDSTONE: As above. SILTSTONE: As above.
	1990 - 1995m	100 Trace	SANDSTONE: As above. SILTSTONE: As above.
	1995-2000m	100	SANDSTONE: As above.
	2000-2005m	100 Trace	SANDSTONE: As above. SILTSTONE: As above.

	2005-2010m	100	SANDSTONE: As above.
	2010-2015m	100	SANDSTONE: As above.
	2015-2020	100	SANDSTONE: As above.
-	2020-2025m	100	SANDSTONE: As above.
	2025-2030m	100	SANDSTONE: Clear, translucent, frosted, predominantly coarse to very coarse grained, angular to subangular unconsolidated fused quartz, similar to above, except slightly altered and fused appearance, no shows.
	2030-2035m	100	SANDSTONE: As above.
_	2035-2040m	100	SANDSTONE: As above.
	2040-2045m	100	SANDSTONE: Clear, glassy, translucent white, clean, coarse to very coarse grained, predominantly angular to occasionally subangular quartz, wholly unconsolidated but individual pieces appear fused or slightly metamorphosed, less faceted, with chaotic crystalline structure, very hard, no shows.
- -	2045-2050m	100	SANDSTONE: As above.
	2050-2055m	100	SANDSTONE: As above.
1	2055-2060m	100	SANDSTONE: As above.
	2060-2065m	100	SANDSTONE: As above.
	2065-2070m	100	SANDSTONE: Shattered glass appearance otherwise as above.
1	2070-2075m	100	SANDSTONE: As above.
I I	2075-2080m	100	SANDSTONE: Greater percentage of finer grained quartz, otherwise as above.
	2080-2085m	100	SANDSTONE: As above.
	2085-2090m	100	SANDSTONE: As above.
	2090-2095m	100	SANDSTONE: As above.
	2095-2100m	70 30 Trace	SANDSTONE: As above. Trace pyrite. COAL: As above. SILTSTONE: As above.
	2100-2105m	90 10	SANDSTONE: As above. SILTSTONE: Light grey, brown, argillaceous, carbonaceous, firm, water sensitive in parts.
!	2105-2110m	50 50	SANDSTONE: As above. SILTSTONE: As above.
!	2110-2115m	60 40	SANDSTONE: As above. SILTSTONE: As above.
	2115-2120m	100	SANDSTONE: As above

2120-2125m	100 Trace	SANDSTONE: White, clear, glassy, frosted, coarse grained, angular to subangular fused quartz grains, slightly altered, good sorting, good to fair inferred porosity, hard, no shows. SILTSTONE: As above.
2125-2130m	80 20	SANDSTONE: As above. SILTSTONE: As above.
2130-2135m	100	SANDSTONE: As above.
2135-2140m	100	SANDSTONE: As above.
2140-2145m	100	SANDSTONE: Clear, translucent, coarse to very coarse grains, occasionally fine to medium grains, poorly sorted, angular to subangular grains, loose quartz, no matrix, no shows.
2145-2150m	100	SANDSTONE: As above.
2150-2155m	100	SANDSTONE: As above.
2155 - 2160m	20 70	SANDSTONE: As above, occasional pyrite. SILTSTONE: dark grey brown, occasionally pale grey, slightly argillaceous, predominantly carbonaceous, scattered black carbonaceous laminae and specks, firm. COAL: As above.
2160-2165m	10 80 10	SANDSTONE: As above. SILTSTONE: As above COAL: As above. CBU @ 2170. No shows. No fluorescence.
2165-2170m	80 20	SANDSTONE: As above. SILTSTONE: As above.
2170-2175m	90 10	SANDSTONE: As above. SILTSTONE: As above.
2175-2180m	100	SANDSTONE: As above.
2180-2185m	100	SANDSTONE: Becoming fine to medium grained quartz and more rounded, otherwise as above.
2185-2190m	100	SANDSTONE: As above.
2190-2195m	100	SANDSTONE: White, translucent, glassy, predominantly fine to medium grained subangular to subrounded slightly altered fused quartz, occasionally coarse angular fused quartz, fair sorting, fair to good inferred porosity, firm, well indurated, no shows.
2195-2200m	100	SANDSTONE: As above.
2200-2205m	100 Trace	SANDSTONE: As above. SILTSTONE: Medium brown, carbonaceous specks, pyritized in parts, friable to firm, arenaceous.
2205-2210m	70 30	SANDSTONE: As above. SILTSTONE: As above (abundant pyrite).
2210-2215m	100 Trace	SANDSTONE: As above. SILTSTONE: As above.

2215-2220m	80 20	SANDSTONE: Clear to translucent, medium to fine to coarse grained, poorly sorted loose angular quartz, no matrix, good to fair inferred porosity, no shows. SILTSTONE: Light grey, light brown occasionally dark brown, arenaceous, carbonaceous in part, friable, firm, pyritic
2220-2225m	60	and blocky. SANDSTONE: As above.
	40	SILTSTONE: As above.
2225-2230m	90 10	SILTSTONE: Grey-brown, brown, light grey, occasionally dark grey, carbonaceous laminae in parts, predominantly carbonaceous, argillaceous, firm to medium hard, soft in parts, blocky, occasionally subfissile, pyritic, no shows. SANDSTONE: As above, occasionally fine grained
		aggregates.
2230-2235m	70 30	SILTSTONE: As above. SANDSTONE: As above.
2235-2240m	90 10	SANDSTONE: White, translucent to clear, clean, predominantly fine to medium grained, subrounded to subangular quartz aggregates in a mainly silica matrix, occasionally coarse to very coarse subangular quartz fragments, poor sorting. No shows. SILTSTONE: As above.
2240-2245m	100	SANDSTONE: As above.
2245-2250m	100	SANDSTONE: As above.
2250-2255m	80 20	SANDSTONE: As above. SILTSTONE: As above.
2255-2260m	70 30	SANDSTONE: As above. SILTSTONE: As above.
2260-2265m	100	SANDSTONE: As above.
2265-2270m	100	SANDSTONE: As above.
2270-2275m	100	SANDSTONE: Increasingly finer subrounded quartz aggregates, otherwise as above.
2275-2280m	90 10	SANDSTONE: As above. SILTSTONE: As above.
2280-228 <i>5</i> m	100	SANDSTONE: As above.
2285-2290m	80	SANDSTONE: Bimodal, clear, translucent, clean, fine to medium grained subrounded to subangular quartz aggregates in a dominantly silica matrix, slightly altered, scattered coarse to very coarse grained subangular quartz fragments, trace pyrite, poor sorting, trace mineral fluorescence. No shows. SILTSTONE: Dark grey/brown, carbonaceous,
	10	slightly argillaceous, firm, no shows. COAL: As above.

2290-2295m	70 30	SANDSTONE: As above. Common pyrite. SILTSTONE: As above.
2295-2300m	80 20	SANDSTONE: As above. SILTSTONE: As above.
2300-230 <i>5</i> m	90 10	SANDSTONE: As above. SILTSTONE: As above.
2305-2310m	100	SANDSTONE: As above.
2310-2315m	70 30	SANDSTONE: As above. SILTSTONE: As above.
2315-2320m	50 5 0	SANDSTONE: As above. SILTSTONE: As above.
2320-2325m	100	SANDSTONE: As above.
2325-2330m	90 10	SANDSTONE: As above. SILTSTONE: As above.
2330 - 233 <i>5</i> m	60 40 Trace	SANDSTONE: White, milky, clear, clean, predominantly fine grained subrounded to subangular quartz aggregates in a silica matrix, scattered coarse to very coarse grained subrounded quartz fragments, very poor sorting, trace mineral calcite fluorescence. No shows. Occasionally pyrite. SILTSTONE: Light grey brown, predominantly argillaceous, with minor carbonaceous flecks throughout, water sensitive in part. COAL: As above.
2335-2340m	80	SANDSTONE: As above.
	20	SILTSTONE: As above.
2340-2345m	50 50	SANDSTONE: As above. SILTSTONE: As above.
2345-2350m	50 50	SANDSTONE: As above. SILTSTONE: As above.
2350-2355m	90 10	SANDSTONE: As above. SILTSTONE: As above.
2355-2360m	90	SANDSTONE: White, clear, clean, medium grained, subrounded to subangular quartz aggregates in a silica matrix, common coarse grained angular quartz fragments, poor sorting, no shows. SILTSTONE: Light grey, predominantly argillaceous, minor carbonaceous, firm.
2360-2365m	100 Trace	SANDSTONE: As above. SILTSTONE: As above.
2365-2370m	90 10	SANDSTONE: As above. SILTSTONE: As above.
2370-2375m	60 40	SANDSTONE: As above. SILTSTONE: Light grey, grey/brown, predominantly argillaceous, carbonaceous, firm, blocky, very carbonaceous in parts grading to coal, pyritic in parts.

2375-2380m	70 30 Trace	SANDSTONE: As above. SILTSTONE: As above. COAL: As above.
2380-2385m	100 Trace	SANDSTONE: white, opaque, translucent, clean, medium to coarse grains, predominantly angular to subangular, occasionally subrounded, quartz aggregates in silica matrix, also loose quartz grains, poorly sorted, trace pyrite. No shows. SILTSTONE: As above.
2385-2390m	90 10 Trace	SANDSTONE: As above. SILTSTONE: grey/brown, dark grey, light grey, very carbonaceous in parts, argillaceous. Soft to firm, blocky, carbonaceous and grading to coal in parts. COAL: As above.
2390-2395m	70 30	SILTSTONE: As above. SANDSTONE: As above.
2395-2400m	50 50	SANDSTONE: As above. SILTSTONE: As above.
2400-2405m	50 50	SANDSTONE: As above. SILTSTONE: As above.
2405-2410m	80 20	SANDSTONE: As above. SILTSTONE: As above.
2410-2415m	60 40	SANDSTONE: White, clear, clean, very coarse grained, subangular quartz fragments, occasionally medium grained subrounded to subangular quartz aggregates, in a dominantly silica matrix, poor sorting, no shows. SILTSTONE: Light brown, beige, micromicaceous, blocky, firm, water sensitive in parts.
2415-2420m	80 20	SILTSTONE: As above. SANDSTONE: As above.
2420-2425m	80 20	SILTSTONE: As above. SANDSTONE: As above.
2425-2430m	70 30	SILTSTONE: As above. SANDSTONE: As above.
2430-2435m	70 30	SANDSTONE: As above. SILTSTONE: As above.
2435 - 2440m	20	SANDSTONE: Clear, white, translucent, medium to very coarse to coarse grained, angular, loose quartz fragments - no matrix, common medium grained subrounded to subangular quartz aggregates in dominantly silica matrix, poor sorting, fair to good porosity. Trace mineral fluorescence. SILTSTONE: Light brown, beige, micromicaceous, predominantly argillaceous, minor carbonaceous, blocky and firm.
2440-2445m	90 10	SANDSTONE: As above. SILTSTONE: As above.

		Ann aids
2445-2450m	90	SANDSTONE: Translucent to clear to white, milky in part, coarse to very coarse grained, angular to subangular, loose quartz grains with no matrix, poorly sorted, 5% white fluorescence, no cut, no crush cut (maybe mineral fluorescence). Also medium grained, subangular to subrounded, loose and silica cemented quartz, no shows, fair to good porosity. SILTSTONE: Light grey to dark grey, brown, micromicaceous, argillaceous, carbonaceous flecks in part, blocky, firm, no shows.
2450-2455m	80 20	SANDSTONE: As above. 5% mineral fluorescence, no cut, no crush cut. SILTSTONE: As above. Becoming more carbonaceous.
2455-2460m	90	SANDSTONE: As above. Less than 5% mineral fluorescence, white to yellow, no cut, no crush cut. Trace residual ring. SILTSTONE: As above.
2460-2465m	90 10 Trace	SANDSTONE: White, translucent, milky, predominantly coarse to very coarse grained, subangular loose quartz aggregates, common medium grained subangular to subrounded quartz aggregates in a dominantly silica matrix, common pyrite, poor sorting, tight to fair inferred porosity; 10% white to white yellow fluorescence with no crush cut, leaves a residual ring of fluorescence after 15 mins. SILTSTONE: As above.
2465-2470m	100 Trace	SANDSTONE: As above. COAL: As above.
2470-2475m	90 10 Trace	SANDSTONE: As above. 5% white-yellow fluorescence with no crush cut, leaves a residual ring of fluorescence. SILTSTONE: As above. COAL: As above.
2475-2480m	60 40	SANDSTONE: As above. Trace mineral fluorescence. SILTSTONE: As above.
2480-2485m	70 30	SANDSTONE: As above. SILTSTONE: As above.
2485 - 2490m	100	SANDSTONE: white, translucent, clear, clean, coarse to very coarse grained with occasional medium grained subangular quartz fragments, no matrix, fair sorting, fair to good inferred porosity, hard, 5% yellow/white mineral fluorescence with no crush cut, but faint residual ring after 15 mins., trace dull red/brown mineral fluorescence.
2490-2495m	100	SANDSTONE: As above.

	2495 - 2500m	70	SILTSTONE: Light grey to grey beige to grey brown, argillaceous, carbonaceous, blocky, soft
		30	to firm, micromicaceous in part. SANDSTONE: As above. Trace yellow mineral fluorescence, no cut.
		Trace	COAL: As above.
	2500-2505m	50 50	SANDSTONE: As above. No mineral fluorescence. SILTSTONE: As above.
	2505-2510m	50	SANDSTONE: As above. Trace fluorescence. No
ŀ		50	cut. SILTSTONE: As above.
	2510-2515m	50	SANDSTONE: As above. Trace fluorescence. No
•		50	cut. SILTSTONE: As above.
	2515 - 2520m	70	SANDSTONE: White, translucent, clear, loose, very coarse grained, subangular quartz fragments, fair sorting, relatively clean, trace to 5% yellow-white fluorescence with very slow diffuse crush cut, residue ring after 15 mins.
		30	SILTSTONE: As above.
1	2520 - 252 5 m	80 20	SANDSTONE: As above. SILTSTONE: As above.
	2525-2530m	90	SANDSTONE: As above. Trace fluorescence with no cut.
		10	SILTSTONE: As above.
	2530-2535m	50 50	SANDSTONE: As above. SILTSTONE: As above
	2535-2540m	50 50	SANDSTONE: As above. SILTSTONE: White/grey, beige, micromicaceous, kaolinitic, carbonaceous, predominantly argillaceous, water sensitive, soft, sticky, no shows.
	2540-254 <i>5</i> m	50 50	SANDSTONE: As above. SILTSTONE: As above.
	2545-2550m	30 70	SANDSTONE: As above. SILTSTONE: As above.
	2550-255 <i>5</i> m	70 30	SANDSTONE: As above. SILTSTONE: Beige, pale brown, predominantly argillaceous, slightly carbonaceous, water sensitive, soft, sticky.
	2555 - 2560m	20	SANDSTONE: White, clear, translucent, relatively clean, predominantly coarse to very coarse grained, loose subangular, occasionally subrounded quartz fragments, scattered medium grained welded quartz aggregates in a dominantly tight silica matrix, trace white-yellow fluorescence with no visible crush cut, trace dull orange dolomitic mineral fluorescence. SILTSTONE: As above.

2560-2565m	80 20	SILTSTONE: As above. SANDSTONE: As above.
2565-2570m	60 40	SILTSTONE: As above. SANDSTONE: As above.
2570-2575m	100	SANDSTONE: As above. No shows.
2575 - 2580m	90	SANDSTONE: White, translucent, clear, unconsolidated, coarse to very coarse grained, subangular to angular quartz fragments, occasionally medium grained subrounded quartz aggregates in a tight silica matrix, fair sorting, good inferred porosity for unconsolidated grains but poor porosity for tightly cemented aggregates, common pyrite crystals, no shows. SILTSTONE: White/beige to light brown, very argillaceous, water sensitive, sticky, scattered carbonacous flecks throughout.
2580-2585m	50 50	SANDSTONE: As above. SILTSTONE: As above.
2585 - 2590m	100 Trace	SILTSTONE: As above. SANDSTONE: As above.
2590-2595m	50 50	SANDSTONE: As above. SILTSTONE: As above.
2595-2600m	20 80	SANDSTONE: As above. SILTSTONE: As above.
2600 - 260 <i>5</i> m	100	SILTSTONE: Pale brown, beige, predominantly argillaceous, water sensitive, soft to occasionally firm, blocky, minor scattered carbonaceous flecks, sticky, no shows.
2605-2610m	60 40	SANDSTONE: As above. SILTSTONE: As above.
2610-2615m	100	SANDSTONE: As above.
2615-2620m	60 40	SILTSTONE: As above; trace shows as for sandstone lithology. SANDSTONE: As above; trace white/yellow fluorescence with no cut to rare very slow diffuse white cut, white residual ring after 15 mins.
2620 – 2625m	90	SANDSTONE: White, translucent, clear, loose, coarse to very coarse grained, subangular quartz fragments, trace pyrite, fair sorting, fair to good inferred porosity, 5% white/yellow fluorescence with very slow diffuse cut, white residue ring after 15 min. SILTSTONE: As above.
2625-2630m	100	SANDSTONE: No shows, otherwise as above.
2630-263 <i>5</i> m	80 20	SANDSTONE: As above. SILTSTONE: As above.
2635-2640m	60 40	SANDSTONE: As above. SILTSTONE: As above.

2640-264 <i>5</i> m	100	SILTSTONE: Pale brown, beige, predominantly argillaceous, trace carbonaceous, water sensitive, sticky, blocky, no shows.
2645-2650m	80 20	SILTSTONE: As above. SANDSTONE: As above.
2650-2655m	80 20	SANDSTONE: As above. SILTSTONE: As above.
2655 - 2660m	100	SANDSTONE: As above; trace dull yellow fluorescence, no crush cut or residue ring.
2660 - 266 <i>5</i> m	100	SANDSTONE: Translucent, white, clear, predominantly subangular to subrounded loose quartz fragments, no matrix, oblique to parallel to random fracturing, occasional pyrite encrustations and coarse pyrite fragments, occasional fracture parting between quartz, poor sorting, fair porosity, 20% moderately bright white yellow fluorescence with only 5% slow diffuse crush cut, trace dolomite mineral fluorescence.
Grab Sample	100	SANDSTONE: As above; 50% relatively bright-yellow fluorescence with slow to moderately diffuse milky-white cut, lithology has greater amounts of fine to medium grained subrounded to subangular aggregates, in a silica to argillaceous matrix.
2666-2670m	90	SANDSTONE: As above. 10% fluorescence, cut as above.
	10	SILTSTONE: As above.
2670-2675m	100	SANDSTONE: As above, trace fluorescence with rare diffuse crush cut.
2675-2680m	100	SANDSTONE: As above.
2680-2685m	100	SANDSTONE: As above.
2685-2690m	90 10	SANDSTONE: As above, trace shows. SILTSTONE: As above.
2690-269 <i>5</i> m	100	SANDSTONE: As above.
2695-2700m	100	SANDSTONE: As above. No shows.
2700-2705m	100	SANDSTONE: White, clear, translucent, coarse to very coarse grained, subangular, loose fragments, with fine to medium grained, subrounded to subangular quartz aggregates in a dominantly silica matrix, occasional argillaceous/kaolinitic white clay matrix, fair sorting, fair inferred porosity, no shows.
2705-2710m	50 50	SANDSTONE: As above. SILTSTONE: As above.
2710-2715m	50 50	SANDSTONE: As above. SILTSTONE: As above.
2715-2720m	80 20	SILTSTONE: As above. SANDSTUNE: As above.

2720-2725m	100	SILTSTONE: Beige, black, light-grey, dark/light-brown, predominantly siliceous to argillaceous matrix, slightly carbonaceous, hard, firm, blocky, grading into very fine grained sandstone, occasionally water sensitive.
2725-2730m	100	SILTSTONE: As above.
2730-2735m	50 50	SANDSTONE: As above. SILTSTONE: As above.
2735-2736m Bottoms up Sample POOH for Core #2	100	SANDSTONE: White, clear, translucent, coarse to very coarse grained, subangular to subrounded, loose quartz fragments, common (20%) fine to medium grained quartz aggregates in a dominantly silica matrix, occasional argillaceous matrix, poor sorting, no fluorescence or cut.
Core #2 2737.1-2755m		See Core Description no. 2.
2755-2760m	80	SANDSTONE: Bimodal, fine to medium grained, subrounded to subangular, quartz aggregates in a dominantly white silica matrix, occasional loose coarse grained subangular quartz grains, poor sorting, relatively tight to occasionally fair porosity, occasional pyrite and biotite, no shows.
	20	SILTSTONE: Dark-grey/brown, argillaceous, micromicaceous, firm, blocky, scattered black carbonaceous laminae.
2760-2765m	60 40	SANDSTONE: As above. SILTSTONE: As above.
2765-2770m	90 10 Trace	SANDSTONE: Dominantly loose, translucent, coarse grained subrounded quartz grains, poorly sorted, occasionally medium grained quartz aggregates in a white silica matrix. SILTSTONE: As above. Pyrite.
2770 – 2775m	100	SANDSTONE: Dominantly quartz, loose, translucent, coarse grained, subangular to subrounded, dominantly subangular, moderately sorted, no matrix, some medium sized quartz aggregates, subrounded to subangular, white silica matrix, poorly sorted. Traces of pyrite, carbonaceous material, biotite and montmorillonite, occasional siltstone (as above).
2775 - 2780m	80	SANDSTONE: Dominantly loose quartz, translucent-transparent, coarse grained, subangular to subrounded poor to moderate sorting. Also quartz aggregates with quartz matrix and trace pyrite, tight porosity.
	20	SILTSTONE: Brown/grey colour, argillaceous, minor carbonaceous, minor mica.

2780-2785m 50 SANDSTONE: Dominantly loose quartz, translucent-transparent, medium to coarse grained, subangular to subrounded, poor to moderate sorting. Quartz aggregates with silica matrix, tiph; borosity, pyrite also within aggregates (minor), minor free pyrite. 50 SINDSTONE: Dominantly loose quartz, translucent transparent, medium to coarse, grained, subangular to subrounded, moderate sorting. Quartz aggregates with silica matrix, tiph; borosity, minor free pyrite. 51 SINDSTONE: Dominantly loose quartz, translucent transparent, medium to coarse, grained, subangular to subrounded, moderate sorting. Quartz aggregates with silica matrix, tiph; borosity, minor free pyrite. 52 SANDSTONE: Dominantly loose quartz, translucent-transparent, medium to coarse grained, subangular to subrounded, poorly sorted. Also quartz aggregates with silica matrix, tight porosity, translucent-transparent, medium to coarse grained, subangular to subrounded, poorly sorted. Also quartz aggregates with silica matrix, tight porosity, tight porosity, translucent pyrite. 52 SANDSTONE: White, fine grained sub-rounded quartz aggregates in a white siliceous matrix, poor sorting, % white/yellow fluorescence with no observable crush cut, otherwise as above. 53 SANDSTONE: Dominantly loose quartz, translucent-transparent, medium to coarse grained, subangular to subrounded, poorly sorted. Aggregates: silica matrix, minor pyrite, tight porosity. 54 SANDSTONE: Pale to dark brown, moderate to firm, minor carbonaceous material, minor free pyrite. 55 SANDSTONE: As above. 56 SANDSTONE: As above. 57 SANDSTONE: As above. 58 SANDSTONE: Translucent to transparent, medium to coarse grained, angular to subengular, poorly sorted, trace white/yellow fluorescence, quartz grains. Aggregates: silica matrix, trace pyrite, tight porosity, minor free pyrite. 58 SANDSTONE: Translucent to transparent, medium to coarse grained, angular to subangular, poorly sorted, trace white/yellow fluorescence, quartz grains. Aggregates: silica matrix, trace pyrite.		
translucent - transparent, medium to coarse, grained, subangular to subrounded, moderate sorting. Quartz aggregates with silica matrix, tight porosity, minor free pyrite. 50 SILTSTONE: Pale to dark brown, firm, micaceous, carbonaceous. 2790-2795m 60 SANDSTONE: Dominantly loose quartz, translucent-transparent, medium to coarse grained, subangular to subrounded, poorly sorted. Also quartz aggregates with silica matrix, tight porosity, trace pyrite. 40 SILTSTONE: Light to dark brown, soft to firm, carbonaceous (minor). 2795-2800m 60 SANDSTONE: White, fine grained sub-rounded quartz aggregates in a white siliceous matrix, poor sorting, 5% white/yellow fluorescence with no observable crush cut, otherwise as above. 51 SANDSTONE: As above. 2800-2805m 60 SANDSTONE: Dominantly loose quartz, translucent-transparent, medium to coarse grained, subangular to subrounded, poorly sorted. Aggregates: silica matrix, minor pyrite, tight porosity. 40 SILTSTONE: Pale to dark brown, moderate to firm, minor carbonaceous material, minor free pyrite. 2805-2810m 60 SANDSTONE: Quartz grains, translucent to transparent, fine to medium grained, subangular to subrounded. Aggregates: silica matrix, minor pyrite, and subrounded. Silica matrix, minor pyrite, tight porosity. Minor free pyrite. 51 SANDSTONE: Translucent to transparent, medium to coarse grained, angular to subangular, poorly sorted, trace white/yellow fluorescence, quartz grains. Aggregates: silica matrix, some is carbonaceous, minor mica. 52 SANDSTONE: translucent to transparent, medium to coarse grained, angular to subangular, some is carbonaceous, minor mica. 53 SANDSTONE: translucent to transparent, medium to coarse grained, angular to subangular, poorly sorted, trace white/yellow fluorescence, quartz grains. Aggregates: silica matrix,	2780 - 2785m	translucent-transparent, medium to coarse grained, subangular to subrounded, poor to moderate sorting. Quartz aggregates with silica matrix, tight porosity, pyrite also within aggregates (minor), minor free pyrite. SILTSTONE: Pale brown to grey, firm,
translucent-transparent, medium to coarse grained, subangular to subrounded, poorly sorted. Also quartz aggregates with silica matrix, tight porosity, trace pyrite. 40 SILSTONE: Light to dark brown, soft to firm, carbonaceous (minor). 2795-2800m 60 SANDSTONE: White, fine grained sub-rounded quartz aggregates in a white siliceous matrix, poor sorting, 5% white/yellow fluorescence with no observable crush cut, otherwise as above. 2800-2805m 60 SANDSTONE: Dominantly loose quartz, translucent-transparent, medium to coarse grained, subangular to subrounded, poorly sorted. Aggregates: silica matrix, minor pyrite, tight porosity. 40 SILTSTONE: Pale to dark brown, moderate to firm, minor carbonaceous material, minor free pyrite. 2805-2810m 60 SANDSTONE: Quartz grains, translucent to transparent, fine to medium grained, subangular to subrounded. Aggregates: silica matrix, minor pyrite. 40 SILTSTONE: As above. 2810-2815m 60 SANDSTONE: Translucent to transparent, medium to coarse grained, angular to subangular, poorly sorted, trace white/yellow fluorescence, quartz grains. Aggregates: silica matrix, trace pyrite, tight porosity, minor free pyrite. 40 SILTSTONE: Pale to dark brown, medium to firm, some is carbonaceous. 2815-2820m 80 SILTSTONE: Pale to dark brown, soft to firm, some is carbonaceous, minor mica. 20 SANDSTONE: translucent to transparent, medium to coarse grained, angular to subangular, poorly sorted, trace white/yellow fluorescence, quartz grains. Aggregates: silica matrix, some is carbonaceous, minor mica.	2785 - 2790m	SANDSTONE: Dominantly loose quartz, translucent - transparent, medium to coarse, grained, subangular to subrounded, moderate sorting. Quartz aggregates with silica matrix, tight porosity, minor free pyrite. SILTSTONE: Pale to dark brown, firm,
quartz aggregates in a white siliceous matrix, poor sorting, 5% white/yellow fluorescence with no observable crush cut, otherwise as above. 2800-2805m 60 SANDSTONE: Dominantly loose quartz, translucent-transparent, medium to coarse grained, subangular to subrounded, poorly sorted. Aggregates: silica matrix, minor pyrite, tight porosity. 40 SILTSTONE: Pale to dark brown, moderate to firm, minor carbonaceous material, minor free pyrite. 2805-2810m 60 SANDSTONE: Quartz grains, translucent to transparent, fine to medium grained, subangular to subrounded. Aggregates: silica matrix, minor pyrite. 40 SILTSTONE: As above. 2810-2815m 60 SANDSTONE: Translucent to transparent, medium to coarse grained, angular to subangular, poorly sorted, trace white/yellow fluorescence, quartz grains. Aggregates: silica matrix, trace pyrite, tight porosity, minor free pyrite. 40 SILTSTONE: Pale to dark brown, medium to firm, some is carbonaceous. 2815-2820m 80 SILTSTONE: Pale to dark brown, soft to firm, some is carbonaceous, minor mica. 20 SANDSTONE: Pale to dark brown, soft to firm, some is carbonaceous, minor mica. 20 SANDSTONE: Pale to dark brown, soft to firm, some is carbonaceous, minor mica. 20 SANDSTONE: Pale to dark brown, soft to firm, some is carbonaceous, minor mica. 20 SANDSTONE: Pale to dark brown, soft to firm, some is carbonaceous, minor mica. 21 SANDSTONE: Pale to dark brown, soft to firm, some is carbonaceous, minor mica. 22 SANDSTONE: Pale to dark brown, soft to firm, some is carbonaceous, minor mica. 23 SANDSTONE: Pale to dark brown, soft to firm, some is carbonaceous, minor mica. 24 SANDSTONE: Pale to dark brown, soft to firm, some is carbonaceous, minor mica. 25 SANDSTONE: Pale to dark brown, soft to firm, some is carbonaceous, minor mica. 26 SANDSTONE: Pale to dark brown, soft to firm, some is carbonaceous, minor mica. 27 SANDSTONE: Pale to dark brown, soft to firm, some is carbonaceous, minor mica. 28 SANDSTONE: Pale to dark brown and the dark brown and the dark brown and the dark brown and the	2790 - 2795m	translucent-transparent, medium to coarse grained, subangular to subrounded, poorly sorted. Also quartz aggregates with silica matrix, tight porosity, trace pyrite. SILSTONE: Light to dark brown, soft to firm,
translucent-transparent, medium to coarse grained, subangular to subrounded, poorly sorted. Aggregates: silica matrix, minor pyrite, tight porosity. 40 SILTSTONE: Pale to dark brown, moderate to firm, minor carbonaceous material, minor free pyrite. 2805-2810m 60 SANDSTONE: Quartz grains, translucent to transparent, fine to medium grained, subangular to subrounded. Aggregates: silica matrix, minor pyrite. 40 SILTSTONE: As above. 2810-2815m 60 SANDSTONE: Translucent to transparent, medium to coarse grained, angular to subangular, poorly sorted, trace white/yellow fluorescence, quartz grains. Aggregates: silica matrix, trace pyrite, tight porosity, minor free pyrite. 40 SILTSTONE: Pale to dark brown, medium to firm, some is carbonaceous. 2815-2820m 80 SILTSTONE: Pale to dark brown, soft to firm, some is carbonaceous, minor mica. 20 SANDSTONE: translucent to transparent, medium to coarse grained, angular to subangular, poorly sorted, trace white/yellow fluorescence, quartz grains. Aggregates: silica matrix,	2795-2800m	quartz aggregates in a white siliceous matrix, poor sorting, 5% white/yellow fluorescence with no observable crush cut, otherwise as above.
transparent, fine to medium grained, subangular to subrounded. Aggregates: silica matrix, minor pyrite. 40 SILTSTONE: As above. 2810-2815m 60 SANDSTONE: Translucent to transparent, medium to coarse grained, angular to subangular, poorly sorted, trace white/yellow fluorescence, quartz grains. Aggregates: silica matrix, trace pyrite, tight porosity, minor free pyrite. 40 SILTSTONE: Pale to dark brown, medium to firm, some is carbonaceous. 2815-2820m 80 SILTSTONE: Pale to dark brown, soft to firm, some is carbonaceous, minor mica. 20 SANDSTONE: translucent to transparent, medium to coarse grained, angular to subangular, poorly sorted, trace white/yellow fluorescence, quartz grains. Aggregates: silica matrix,	2800-2805m	translucent-transparent, medium to coarse grained, subangular to subrounded, poorly sorted. Aggregates: silica matrix, minor pyrite, tight porosity. SILTSTONE: Pale to dark brown, moderate to firm, minor carbonaceous material, minor free
to coarse grained, angular to subangular, poorly sorted, trace white/yellow fluorescence, quartz grains. Aggregates: silica matrix, trace pyrite, tight porosity, minor free pyrite. 40 SILTSTONE: Pale to dark brown, medium to firm, some is carbonaceous. 2815-2820m 80 SILTSTONE: Pale to dark brown, soft to firm, some is carbonaceous, minor mica. 20 SANDSTONE: translucent to transparent, medium to coarse grained, angular to subangular, poorly sorted, trace white/yellow fluorescence, quartz grains. Aggregates: silica matrix,	2805-2810m	transparent, fine to medium grained, subangular to subrounded. Aggregates: silica matrix, minor pyrite.
some is carbonaceous, minor mica. 20 SANDSTONE: translucent to transparent, medium to coarse grained, angular to subangular, poorly sorted, trace white/yellow fluorescence, quartz grains. Aggregates: silica matrix,	2810-2815m	to coarse grained, angular to subangular, poorly sorted, trace white/yellow fluorescence, quartz grains. Aggregates: silica matrix, trace pyrite, tight porosity, minor free pyrite. SILTSTONE: Pale to dark brown, medium to firm,
	2815-2820m	some is carbonaceous, minor mica. SANDSTONE: translucent to transparent, medium to coarse grained, angular to subangular, poorly sorted, trace white/yellow fluorescence, quartz grains. Aggregates: silica matrix,

Core Descriptions

Core No.

1165.4m - 1175.2m Interval Cored:

Cut 9.8m

Recovered : 7.6m (78%) Bit Type PVL RC 476 : 9-7/8 UD and 4-3/4 ID Bit Size

Well


Described by Jeff Roche Date : 14.08.85

Depth &

ROP Graphic Shows Int.

Descriptive Lithology

: WHIPTAIL-1A



1165.4-1166.0m SANDSTONE - white, clear, frosted, clean, unconsolidated to friable, predominantly fine to occasionally medium grained, subrounded to occasionally subangular, relatively mature quartz, with mica/muscovite flakes. Excellent sorting, excellent inferred porosity, no visible fluorescence or oil, slight petroliferous odour; trace subangular, coarse to very coarse grained, quartz fragments scattered throughout.

1166.0-1169.0m SANDSTUNE - no petroliferous odour, otherwise as above.

medium to coarse grained, subangular quartz grains, trace mica, excellent sorting, excellent inferred porosity, minor dolomitic mineral fluorescence, no shows.

Interpreted as a clean relatively mature marine sandstone.

Core No. 2 Well : WHIPTAIL-1A

Interval Corea : 2737.2m - 2754.6m


Cut : 17.4m Recovered : 9.8m (56.3%)

Bit Type : RC4 Bit Size : 9/7-8" UD and 4-3/4" ID

Described by : Jeff Roche Date : 26.8.85

Depth & .

Int. ROP Graphic Shows Descriptive Lithology



2737.2 - 2738.2m SANUSTONE - grains are clear, grey, translucent, medium to occasional coarse, subangular, fairly sorted, white crystalline, poor to fair visual porosity; sucrosic silica cement; overall relatively friable but some firm to hard, occasional loose, coarse, angular to subangular grains, black biotite and very coarse yellow pyrite pieces distributed throughout. reddish-brown altered garnet-like crystals or mafic minor shale concretions present. Porosity depends on amount of cement. No shows. Massive to faintly parallel bedding near the base. Bedding planes are not particularly distinct, but generally are parallel at base with subtle festoon cross bedding towards the top. Fining upward sequence, probably moderately high energy environment, possibly bioturbated.

2738.2 - 2743.3m SHALEY SILTSTONE massive medium dark grey, hard to very hard, firm, moderately micromicaceous, slightly argillaceous, very carbonaceous, non calcareous with abundant medium grained rounded biotite which is evenly distributed. Minor flat peat fragments and coarse quartz pieces from erosional base at 2743.3 m up to 2739 m. Grades to a black massive, non-fissile bituminous shale above 2739 m, with very fine yellow disseminated pyrite and occasional reddish brown altered mafics. Sharp contacts with both overlying and underlying sandstone sequences.

2743.3 - 2745.5m SILTY SANDSTONE - stacked fining upward sequences, grading from medium to occasional coarse grained sandstone at the base, through to finely laminated siltstone and sandstone layers near the mid sections at 2944.6 m. This 2744.6 cycle is repeated before truncation by the overlying siltstone sequence which abbreviates the cycle. Uverall the sandstone is clear, translucent, grey, subrounded to subangular in a white subcrystalline siliceous matrix, hard, firm fair sorting with fair visual porosity.

Core No. 2 cont'a well

: WHIPTAIL-1A

Interval Coreo : 2737.2m - 2754.6m

17.4m

KC4

Cut Bit Type Described by : Jeff Roche Recovered Bit Size

(56.3%)

: 9.8m : 9/7-8" UD and 4-3/4" ID

Date : 26.8.85

Descriptive Lithology

2743.3-2745.5m cont'a - No shows. At 2743.5, black vitreous subangular coal clasts evenly distributed throughout the siliceous sandstone. Fine carbonaceous laminae define the horizontal and inclined parallel laminations, ranging from 30° near the base to 5° near the top of the sequence representing low energy current ripples and small scale cross-beds. Scattered discontinuous flat peat lenses of less than 1 cm occur throughout. Occasional parallel lenticular coarse grained sandstone lenses cut across a predominantly massive medium grained sandstone matrix at 2744.5 m. Black, fine, coal laminae near the base at 2745.6 m defines parallel bedding planes ranging from $15-20^{\circ}$.

2745.5 - 2747.0m SANDSTONE - massive, clear, translucent, grey, medium grained subrounded quartz in a sub crystalline siliceous matrix, firm, hard, clean, good sorting, poor to fair visual porosity, faintly laminated with subtle cross bedding throughout. No shows.

2747-2754.6m No recovery

Sidewall Core Descriptions

WHIPTAIL-1A

SIDEWALL CORE DESCRIPTIONS

•	No.	<u>Depth</u>	Rec.	Rock Type	Description
	1	2781.0		SILTSTONE	light grey, well sorted, soft; quartzose, argillaceous.
	2.	2715.0		SILTSTONE	light grey, well sorted, soft; quartzose, argillaceous.
	3	2712.0		SILTSTONE	dark grey, moderately sorted, soft; argillaceous, coaly.
	4	2676.1		SANDSTONE	grey, fine grained, moderately sorted, subrounded, friable; carbonaceous, coaly.
	5	2666.0		SANDSTONE	white grey, fine grained, moderately sorted, subrounded, friable; carbonaceous.
	6	2653.5		SANDSTONE	white grey, fine to medium grained, well sorted, subrounded, friable; carbonaceous, coaly.
	7	2634.0		SANDSTONE	light grey, fine grained, moderately sorted, subrounded, friable; argillaceous, carbonaceous; 30% fluorescence.
	8	2618.0		SANDSTONE	light grey, medium grained, well sorted, friable; argillaceous; 30% spotty bright blue white fluorescence; very faint pale white cut; Cl-C3, only trace C4.
	9	2600.0		CLAYSTONE	light brown, soft; argillaceous.
	10	2547.1		SILTSTONE	dark brown, hard; carbonaceous, argillaceous.
	11	2476.5		CLAYSTONE	dark brown, firm; carbonaceous, argillaceous.
]	12	2452.1		SANDSTONE	white, fine to medium grained, well sorted, subrounded, friable; slightly argillaceous; 100% even bright white fluorescence; bright white cut; C1-C3, only trace C4.
	13	2415.0	,	SILTSTONE	light brown, well sorted, soft; argillaceous, quartzose.
•	14	2361.8		NO RECOVERY	
 	15	2292.8		SANDSTONE	grey, fine grained, moderately sorted, subrounded, friable; carbonaceous, trace mica.

1	6	2245.1	SANDSTONE	grey, fine grained, moderately sorted, subrounded, friable; carbonaceous trace, mica.
1	.7	2218.3	CLAYSTONE	dark brown, firm; argillaceous, carbonaceous.
1	8	2163.0	NO RECOVERY	
1	9	2126.4	SANDSTONE	grey, fine to medium grained, poorly sorted, subrounded, friable; argillaceous, carbonaceous.
2	0	2099.5	SANDSTONE	white, fine to medium grained, well sorted, subrounded, friable; mica.
2.	1	2006.3	SANDSTONE	grey to white, fine to medium grained, well sorted, subrounded, friable; slightly carbonaceous.
2	2	2090.0	SANDSTONE	grey to white, fine grained, moderately sorted, subrounded, friable; mica.
2.	3	2060.8	SANDSTONE	grey to white, fine to medium grained, moderately sorted, subrounded, friable; carbonaceous.
24	4	1992.5	SANDSTONE	grey to white, fine to medium grained, moderately sorted, subrounded, friable; carbonaceous, trace mica.
2:	5	1940.1	SANDSTONE	grey to white, fine grained, well sorted, subrounded, friable; trace mica.
20	6	1864.0	SANDSTONE	grey to white, fine grained, well sorted, subrounded, friable; trace mica.
2	7	1810.9	SILTSTONE	dark grey, firm; carbonaceous, argillaceous.
28	8	1735.1	SANDSTONE	light grey, fine grained, well sorted, subrounded, friable; carbonaceous, trace mica.
25	9	1698.0	SANDSTONE	light grey, fine grained, well sorted, subrounded, friable; carbonaceous.
30	0	1660.0	SANDSTONE	white, fine grained, well sorted, subrounded, friable; pyritic, trace mica.
3]	1	1635.2	CLAYSTONE	light brown, firm; argillaceous.
32	2	1589.5	SANDSTONE	white, fine grained, well sorted, subrounded, trace mica.
33		1580.0	SANDSTONE	light grey, fine grained, moderately sorted, subrounded, friable; trace mica, carbonaceous.

J				
	34	1571.8	SILTSTONE	white, well sorted, firm to soft, quartzose.
	35	1501.5	SILTSTONE	grey, well sorted, firm, quartzose.
	36	1478.0	CLAYSTONE	grey, firm, argillaceous, silty.
	37	1451.8	SILTSTONE	white, well sorted, firm, quartzose, trace mica, coaly.
1	<i>3</i> 8	1447.1	COAL	black, brittle.
	39	1431.0	NO RECOVERY	•
	40	1409.5	VERY FINE SANDSTONE- SILTSTONE	white grey, very fine to fine grained, moderately sorted, firm, quartzose, trace mica, carbonaceous.
	41	1402.0	SANDSTONE	white, fine grained, well sorted, friable; trace mica.
	42	1383.5	SANDSTONE	white, fine grained, well sorted, friable; trace mica.
	43	1382.6	SILTSTONE- VERY FINE SANDSTONE	grey to black, very fine to fine grained, poorly sorted, firm; quartzose, carbonaceous, coaly.
	44	1381.5	SILTSTONE	dark brown, firm, carbonaceous, trace mica.
	45	1380.0	SANDSTONE	dull white, very fine to fine grained, well sorted, subrounded, friable; mica; 80% even, relatively bright white fluorescence, relatively bright white cut; Cl-C4 only.
	46	1375.6	SILTSTONE	dark brown, hard, carbonaceous, coaly.
	47	1360.0	NO RECOVERY	
l	48	1344.0	SILTSTONE	light grey, firm; quartzose, carbonaceous.
	49	1312.0	SILTSTONE	light grey, firm; quartzose, carbonaceous.
	50	1278.0	SILTSTONE	dark grey to black, firm; carbonaceous, trace mica.
	51	1257.5	CLAYSTONE	pale brown, firm, argillaceous, silty.
	52	1228.6	CLAYSTONE	dark brown, firm, very argillaceous, carbonaceous.
· 	53	1202.5	SILTSTONE	black, hard, carbonaceous.
	54	1164.0	SANDSTONE	white to grey, fine grained, subrounded, friable; carbonaceous.

•

- 4 -

55	1154.7	STEISTUNE	black, firm, carbonaceous.
56	1147.8	SILTSTONE	black, firm, carbonaceous.
57	1141.3	NO RECOVERY	
58	1134.7	SILTSTONE	dark brown, firm, carbonaceous, moderately calcareous.
59	1128.5	SILTSTONE	dark brown, firm, carbonaceous, moderately calcareous.
60	1120.0	SILTSTONE	dark brown, firm, carbonaceous, moderately calcareous.

Sidewall Core Gas Analysis

WHIPTAIL #1A
SIDEWALL CORE GAS ANALYSIS

NO.	DEPTH (m)	Cl	C2	C3	C4	C5	C6
4	2676.0	1133	36	16	TR		
5	2666.0	785	10				
6 8	2653.5	1918	35 70	10	TR		
8	2618.0	2163	30 33	8	TR		
12	2412.0	2420	33	8	TR		
20	2099.5	3208	46 31	11 8	TR TD		***
22	2090.0	2371	31 44		TR TR		
41	1402.0	3139	44 30	11	TR		
42 45	1383.5 1380.0	2232 2098	39 39	11 8	TR		
45 15	2292.8	802	14	TR	117		
25	1940.0	786	11				
26	1864.0	700 3139	52	12	TR		
28	1735.0	2964	46	11	ŤŘ		
29	1698.0	2092	30	8	TR		
33	1580.0	2058	33	8	TR		
23	2060.8	1918	35	8	TR		
24	1992.5	2441	47	10	TR		
19	2126.0	TR					
32	1589.5	3488	60	14	TR		
16	2245.0	2232	33	8	TR		

TOTAL 21 SAMPLES

1848L/54

RFT Results

RFT SAMPLE TEST REPORT

Well : Whiptail-lA

OBSERVER : Jeff Roche

DATE : 18 August 1985 RUN NO. : One

BSEI	RVER : Jett Roche	DATE	: 10 August	1707 1017 110.	OI IE
		CHAMBER 1 (22 7 li+)	CHAMBER 2 (10.	4 lit.)
CE O	T NO.	1/1	22.7 116.7	1/1	- 110./
		1397.5		1397.5	
DEP		1 1297.2		1221.0	
Α.	RECORDING TIMES	1 // 20		<u> </u>	
	Tool Set	1428		1 1 4 4 0	
	Pretest Open	1428		1449	
	Time Open	4			
	Chamber Open	1432		1450	
	Chamber Full	1443		1453	
	Fill Time	11		3	
	Start Build Up	1443		1453	
	Finish Build Up	1446		1457	
	Build Up Time	3		4	
	Seal Chamber	1448		1458	
		1 1440		1459	
	Tool Retract	00		·	
	Total Time	20 mins.		9 mins.	
В.	SAMPLE PRESSURE	 			
	IHP	2347	psig		psig
	ISIP	1979	psig	1971	psig
	Initial Flowing Press.	1767	psig	1514	psig
	Final Flowing Press.	1888	psig	1943	psig
	Sampling Press. Range	121	psig	429	psig
	FSIP	1971	hata	1972	
		I 17/1			psig
	FHP			2342	psig
	Form.Press.(Horner)			<u> </u>	psig
C.	TEMPERATURE				
	Depth Tool Reached	1450	m		m
	Max. Rec. Temp	66.4	deg C		deg C
	Time Circ. Stopped	23.25/17th	hrs.		hrs.
	Time since Circ.	15	hrs.		hrs.
	Time Since Circ.	<u> </u>	deg C		
	Form.Temp.(Horner)		deg C	<u> </u>	psig
<u>D.</u>	SAMPLE RECOVERY				
	Surface Pressure	325	psig		psig
	Amt Gas	0.71	cu ft	-	lit.
	Amt Oil	22,00	lit	9.60	lit.
	Amt Water	_	lit	_	lit.
	Amt Others (Filtrate)	Trace	lit.		lit.
		1 11466	4100		
<u> </u>	SAMPLE PROPERTIES			<u> </u>	
	Gas Composition	 		! 	
	<u>C1</u>	45,043	ppm	<u> </u>	bbw
	C2	4,220	ppm	-	ppm
	C3	4,493	ppm	-	ppm
	IC4/nC4	1,997	ppm	-	ppm
	C5	441	ppm	_	ppm
	C6+	110	ppm	<u> </u>	ppm
	CO2/H2S	-/-	ppm	-/-	ppm
O: 1					ppiii
<u>UIL</u>	Properties	37 deg API@		42 deg API@ 15	deg C
	Colour	Reddish Brow		Reddish Brown	
	Fluorescence	Bright White	}	Bright White	
	GOR	5 SCF/BBL			
Wate	er Properties				
	Resistivity	0.377 ohm-m	@ 14 deg C	<u>@</u>	deg C
	NaCl Equivalent	21,000	ppm		ppm
	Cl-titrated	12,500			
			ppm	<u> </u>	ppm
	Tritium		Rec: 2876 DPM	 	DPM
	Est Water Type	Filtrate		<u> </u>	
Mud	Filtrate Properties				
	Resistivity	.295 ohm-m @	16 deg C	ohm-m@	deg C
	NaCl Equivalent	25,000	ppm		ppm
	Cl-titrated	17,000	ppm		ppm
Cal.	ibration		FF.''		_ F
Jar.	Calibration Press.	<u> </u>			
				<u> </u>	
	Calibration Temp.			, , , , , , , , , , , , , , , , , , ,	
	Hewlett Packard No.				
	Mud Weight	9.8	ppg	9.8	ppg
	Calc.Hydrostatic	9.8	ppg	9.8	ppg
	Chokesize/Probe Type	1 x .030"/		1 x .030"/M	
RFM/	ARKS				
		i İ			
	l l	 			
				Ī	

Well : Whiptail-lA

OBSERVER : Jeff Roche

DATE : 18 August 1985 RUN NO. : Two

CHAMBER 1 (22.7 lit.) CHAMBER 2 (SEAT NO. 2/2	10.4 lit.)
DEPTH	
A. RECORDING TIMES	
Tool Set	
Pretest Open	
Time Open	
Chamber Open	
Chamber Full	
Fill Time	
Start Build Up	
Finish Build Up	
Build Up Time	
Seal Chamber 1751	**************************************
Tool Retract	
Total Time	
B. SAMPLE PRESSURE	
IHP	
ISIP	peig
Initial Flowing Press. 1835 1707 Final Flowing Press. 1939 1949 1949 1954 1	psig psig
Final Flowing Press. 1939 1949 Sampling Press. Range 106 242 FSIP 1954 1954 1954 1954 FSIP 2311 Form.Press.(Horner) C. TEMPERATURE Depth Tool Reached m deg C Time Circ. Stopped 23.25/17th hrs. Time since Circ. 18 hrs. Form.Temp.(Horner) deg C D. SAMPLE RECOVERY Surface Pressure 575 psig Amt Gas 0.2 cu ft Amt Others (Filtrate) 5.25 lit. E. SAMPLE PROPERTIES Gas Composition C1 NOT ENOUGH ppm C2 GAS ppm C3 T0 ppm C4/nC4 MEASURE ppm C5 ppm C6+ ppm C02/H2S ppm C02/H2S ppm C02/H2S ppm C02/H2S ppm C01 Properties 41 deg API@ 20 deg C API@ CO1 Poperties 41 deg API@ 20 deg C API@ C1 Poperties Popert	
Sampling Press. Range 106 242 FSIP 1954	psig
FSIP	psig
FHP	psig
Form.Press.(Horner) C. TEMPERATURE Depth Tool Reached m Max. Rec. Temp deg C Time Circ. Stopped 23.25/17th hrs. Time since Circ. 18 hrs. Form.Temp.(Horner) deg C D. SAMPLE RECOVERY Surface Pressure 575 psig Ant Gas 0.2 cu ft Amt Oil 16.30 lit Amt Water lit Amt Others (Filtrate) 5.25 lit. E. SAMPLE PROPERTIES Gas Composition Cl NOT ENOUGH ppm C2 GAS ppm C3 T0 ppm C4/nC4 MEASURE ppm C6+ ppm C6+ ppm C02/H2S ppm C1 Properties 41 deg API@ 20 deg C API@ C0 C1 Honey Brown Fluorescence Bright White GOR 2 SCF/BBL Water Properties Resistivity 0.342 ohm-m @ 14 deg C @ NaCl Equivalent 23,000 ppm C1-titrated 14,500 ppm C1-titrated	psig
C. TEMPERATURE	psig
Depth Tool Reached	psig
Max. Rec. Temp deg C Time Circ. Stopped 23.25/17th hrs. Time since Circ. 18 hrs. Form.Temp.(Horner) deg C D. SAMPLE RECOVERY Deg C Surface Pressure 575 psig Amt Gas 0.2 cu ft Amt Oil 16.30 lit Amt Water - lit Amt Others (Filtrate) 5.25 lit. E. SAMPLE PROPERTIES Gas Composition C1 C2 GAS ppm C3 TO ppm C3 TO ppm C6+ ppm C6+ C02/H2S ppm Degree Oil Properties 41 deg API@ 20 deg C API@ Colour Honey Brown Fluorescence Bright White GOR 2 SCF/BBL Water Properties Resistivity 0.342 ohm-m @ 14 deg C @ NaCl Equivalent 23,000 ppm C1-titrated 14,500 ppm	
Time Circ. Stopped 23.25/17th hrs. Time since Circ. 18 hrs. Form.Temp.(Horner) deg C D. SAMPLE RECOVERY Surface Pressure 575 psig Amt Gas 0.2 cu ft Amt Oil 16.30 lit Amt Water - lit Amt Others (Filtrate) 5.25 lit. E. SAMPLE PROPERTIES Gas Composition C1 NOT ENOUGH ppm C2 GAS ppm C3 TO ppm C4/nC4 MEASURE ppm C5 ppm Co2/H2S Oil Properties 41 deg API@ 20 deg C API@ Colour Honey Brown Fluorescence Bright White GOR 2 SCF/BBL Water Properties Resistivity 0.342 ohm-m @ 14 deg C @ NaCl Equivalent 23,000 ppm C1-titrated 14,500 ppm	m doa C
Time since Circ.	deg C
Form.Temp.(Horner) deg C	hrs.
D. SAMPLE RECOVERY Surface Pressure 575 psig Amt Gas 0.2 cu ft Amt Oil 16.30 lit Amt Water - lit Amt Others (Filtrate) 5.25 lit. E. SAMPLE PROPERTIES Gas Composition C1 NOT ENOUGH ppm C2 GAS ppm C3 T0 ppm C4/nC4 MEASURE ppm C5 ppm C6+ ppm C02/H2S ppm C01/H2S ppm C1 Properties 41 deg API@ 20 deg C API@ C1 Properties Bright White GOR 2 SCF/BBL Water Properties Resistivity 0.342 ohm-m @ 14 deg C @ NaCl Equivalent 23,000 ppm C1-titrated 14,500 ppm	hrs.
Surface Pressure	psig
Amt Gas	
Amt Oil 16.30 lit Amt Water - lit Amt Others (Filtrate) 5.25 lit. E. SAMPLE PROPERTIES Gas Composition C1 NOT ENOUGH ppm C2 GAS ppm C3 TO ppm IC4/nC4 MEASURE ppm C5 ppm C6+ ppm C02/H2S ppm Oil Properties 41 deg API@ 20 deg C API@ Colour Honey Brown Fluorescence Bright White GOR 2 SCF/BBL Water Properties Resistivity 0.342 ohm-m @ 14 deg C @ NaCl Equivalent 23,000 ppm Cl-titrated 14,500 ppm	psig
Amt Water - lit Amt Others (Filtrate) 5.25 lit. E. SAMPLE PROPERTIES Gas Composition C1 NOT ENOUGH ppm C2 GAS ppm C3 TO ppm IC4/nC4 MEASURE ppm C5 ppm C6+ ppm C02/H2S ppm C01 Properties 41 deg API@ 20 deg C API@ Colour Honey Brown Fluorescence Bright White GOR 2 SCF/BBL Water Properties Resistivity 0.342 ohm-m @ 14 deg C @ NaCl Equivalent 23,000 ppm C1-titrated 14,500 ppm	lit.
Amt Others (Filtrate) 5.25 lit. E. SAMPLE PROPERTIES Gas Composition C1 NOT ENOUGH ppm C2 GAS ppm C3 TO ppm IC4/nC4 MEASURE ppm C5 ppm C6+ ppm C02/H2S ppm C1 Properties 41 deg API@ 20 deg C API@ C1 API@ C2 Fight White C3 API@ C4 API@ C5 API@ C5 API@ C6 API@ C7 API@ C8 API@ C9 API@ C1 API@ C1 API@ C1 API@ C2 API@ C3 API@ C4 API@ C5 API@ C5 API@ C6 API@ C7 API@ C7 API@ C8 API@ C9 API@ C9 API@ C1 API	lit.
Cas Composition	lit.
Gas Composition C1	lit.
C1 NOT ENOUGH ppm C2 GAS ppm C3 TO ppm IC4/nC4 MEASURE ppm C5 ppm C6+ ppm C02/H2S ppm C01 Properties 41 deg API@ 20 deg C API@ Colour Honey Brown Fluorescence Bright White GOR 2 SCF/BBL Water Properties Resistivity 0.342 ohm-m @ 14 deg C @ NaCl Equivalent 23,000 ppm C1-titrated 14,500 ppm	
C2 GAS ppm C3 TO ppm IC4/nC4 MEASURE ppm C5 ppm C6+ ppm C02/H2S ppm C02/H2S ppm C1 roperties 41 deg API@ 20 deg C API@ C010ur Honey Brown Fluorescence Bright White GOR 2 SCF/BBL Water Properties Resistivity 0.342 ohm-m @ 14 deg C @ NaCl Equivalent 23,000 ppm C1-titrated 14,500 ppm	
C3	ppm
IC4/nC4 MEASURE ppm C5 ppm C6+ ppm C02/H2S ppm C02/H2S ppm Oil Properties 41 deg API@ 20 deg C API@ Colour Honey Brown Fluorescence Bright White GOR 2 SCF/BBL Water Properties Resistivity 0.342 ohm-m @ 14 deg C @ NaCl Equivalent 23,000 ppm C1-titrated 14,500 ppm	ppm
C5	ppm
C6+ ppm C02/H2S ppm Dil Properties 41 deg API@ 20 deg C API@ Colour Honey Brown Fluorescence Bright White GOR 2 SCF/BBL Water Properties Resistivity 0.342 ohm-m @ 14 deg C @ NaCl Equivalent 23,000 ppm C1-titrated 14,500 ppm C1-titrated C1-titra	ppm
CO2/H2S ppm Oil Properties 41 deg API@ 20 deg C API@ Colour Honey Brown Fluorescence Bright White GOR 2 SCF/BBL Water Properties Resistivity 0.342 ohm-m @ 14 deg C @ NaCl Equivalent 23,000 ppm Cl-titrated 14,500 ppm	ppm
Oil Properties 41 deg API@ 20 deg C API@ Colour Honey Brown Honey Brown Fluorescence Bright White Bright White GOR 2 SCF/BBL Water Properties Water Properties Resistivity 0.342 ohm-m @ 14 deg C @ NaCl Equivalent 23,000 ppm Cl-titrated 14,500 ppm	ppm
Colour Honey Brown Fluorescence Bright White GOR 2 SCF/BBL Water Properties 0.342 ohm-m @ 14 deg C 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	ppm C
Fluorescence Bright White GOR 2 SCF/BBL Water Properties 0.342 ohm-m @ 14 deg C @ NaCl Equivalent 23,000 ppm Cl-titrated 14,500 ppm	deg C
GOR 2 SCF/BBL Water Properties 0.342 ohm-m @ 14 deg C @ NaCl Equivalent 23,000 ppm Cl-titrated 14,500 ppm	
Water Properties Resistivity NaCl Equivalent Cl-titrated Resistivity 0.342 ohm-m @ 14 deg C @ ppm Cl-titrated 14,500 ppm	
Resistivity 0.342 ohm-m @ 14 deg C @ NaCl Equivalent 23,000 ppm Cl-titrated 14,500 ppm	
NaCl Equivalent 23,000 ppm Cl-titrated 14,500 ppm	deg C
Cl-titrated 14,500 ppm	
	ppm
	ppm DPM
Mud Filtrate Properties Resistivity .295 ohm-m @ 16 deg C ohm@	deg C
	ppm
Cl-titrated 17,000 ppm Calibration	ppm
Calibration Press.	
Calibration Temp.	
	
Hewlett Packard No. Mud Weight 9.8 ppg	000
	ppg
Calc.Hydrostatic 9.8 ppg Chokesize/Probe Type 1 x .030"/Martineau 1 x .030"/Ma	nn-a
REMARKS CH. MBER	ppg
REMARKS CR. INDER	ppg rtineau
I I I I I I I I I I I I I I I I I I I	ppg rtineau

RFT SAMPLE TEST REPORT

Well : Whiptail-lA

OBSERVER : Jeff Roche

DATE : 18 August 1985 RUN NO. : Three

~~~~	r No	CHAMBER 1 (	22.7 lit.)	CHAMBER 2 ()	LO.4 lit.
	ΓNO.	3/3		3/3	
EPI	·	1285.5		1285.5	
١.	RECORDING TIMES	2113			
	Tool Set	1 2114	<u> </u>		
	Pretest Open	1 2114	<u></u>		
	Time Open Chamber Open	!   2117	<del></del>	2131	<del> </del>
	Chamber Full	2126		2134	
	Fill Time	9	<del> </del>	<u>2174</u> 3	
	Start Build Up	1 2126		2134	
	Finish Build Up	1 2129	<u> </u>	2136	····
	Build Up Time	3		2176	
	Seal Chamber	2130	<del></del>	2137	<del></del>
	Tool Retract	1 2170	<u> </u>	2138	
	Total Time	<u>.</u> 17	mins.	7	mins
	SAMPLE PRESSURE	! <u> </u>	IIITI 12 •		1117112
<u>·-</u>	IHP	2159	psig		psig
	ISIP	1821	psig	1819	
	Initial Flowing Press.	1805	<del></del>	1794	psig
	Final Flowing Press.	1810	psig	1800	psig
		5	psig	6	psig
	Sampling Press, Range FSIP	1819	psig	1821	psig
	FHP	1 1013		2161	psig
	Form.Press.(Horner)	<u> </u>	<u> </u>	<u> </u>	psig
•	TEMPERATURE	<u> </u>	<u> </u>		psig
•	Depth Tool Reached	<u> </u>			
		! 	m dog C		m dea (
	Max. Rec. Temp	07 05 /1 744	deg C		deg (
	Time Circ. Stopped	23,25/17th	hrs.		hrs.
	Time since Circ.	22	hrs.	<del> </del>	hrs.
	Form. Temp. (Horner)	<u> </u>	deg C		psig
•	SAMPLE RECOVERY	(00			
	Surface Pressure	600	psig	·	psig
	Amt Gas	0.64	cu ft		lit.
	Amt Oil	0. 50	<u>lit</u>		<u>lit.</u>
	Amt Water	21.50	lit	9.70	lit.
	Amt Others (Filtrate)	 	lit.		lit.
	SAMPLE PROPERTIES	<u> </u>			<del></del>
	Gas Composition		ļ		
	C1 C2		ppm		ppm
		<del> </del>	ppm i		ppm
	C3		ppm		ppm
	. TC4/nC4		ppm I		ppm
	C5		ppm	<del></del>	ppm
	C6+		ppm		ppm
• •	CO2/H2S	 	ppm	ADTO	ppm
	Properties	API@	deg C	API@	deg (
	Colour	<u> </u>		· · · · · · · · · · · · · · · · · · ·	
	Fluorescence				
	GOR	<u> </u>			
	r Properties	0 757	12 1		
	Resistivity	0.653 ohm-m @		0.996 @ 1	
	NaCl Equivalent	12,000	ppm	9,000	ppm
	Cl-titrated	9,000	ppm	7,000	ppm
	Tritium	In: 3U5U DPM I	Rec: 1467 DPM	Rec 855	DPM
	Est Water Type	Filtrate/Forma	tion Water	Formation W	ater
	Filtrate Properties				
	Resistivity	.295 ohm-m (		ohm@	deg C
	NaCl Equivalent	25,000			ppm
	Cl-titrated	17,000	ppm i		ppm
	bration				
	Calibration Press.	· · · · · · · · · · · · · · · · · · ·		-	
	Calibration Temp.	66.6	deg C		
	Hewlett Packard No.				
	<del></del>				
	Mud Weight !	9.8	ppg		ppg
	Mud Weight Calc.Hydrostatic Chokesize/Probe Type	9.8 9.9 1 x .030"/N	ppq	1 x .030"	ppg

#### RFT SAMPLE TEST REPORT

Well : Whiptail-l

OBSERVER : Jeff Roche DATE : 18 August 1985 RUN NO. : Four

			(22.7 lit.)	CHAMBER 2	(10.4 lit.
	T NO.	4/4		4/4	
DEP.		1295.0		1295.0	
Α.	RECORDING TIMES Tool Set	2323			
	Pretest Open	2323			
	Time Open	7			<del> </del>
	Chamber Open	2330		2344	
	Chamber Full	2339		2347	
	Fill Time	9		3	
	Start Build Up	2340		2347	
	Finish Build Up	2343		2350	<del> </del>
	Build Up Time	3		3	
	Seal Chamber	2344		2352	
	Tool Retract			2353	
	Total Time	21	mins.	9	
В.	SAMPLE PRESSURE				
	IHP	2173	psig		psig
	ISIP	1833	psig	1828	psig
	Initial Flowing Press.	1808	psig	1389	psig
	Final Flowing Press.	1822	psig	1797	psig
	Sampling Press. Range	14	psig	408	psig
	FSIP	1828	"	1831	psig
	FHP			2172	psig
	Form.Press.(Horner)				psig
С.	TEMPERATURE				
	Depth Tool Reached		m deg C		m deg C
_	Max. Rec. Temp Time Circ. Stopped	23.25/17th			hrs.
	Time circ. Stopped Time since Circ.	24	hrs.		hrs.
	Form. Temp. (Horner)	1 24	deg C		psig
5.	SAMPLE RECOVERY	<u> </u>	ueg o		ps±g
<del></del>	Surface Pressure	600	psig	-	psig
	Amt Gas	-	lit.	_	lit.
	Amt Oil		lit		lit.
	Amt Water	21.50	lit	9.750	lit.
	Amt Others (Filtrate)		lit.		lit.
Ξ.	SAMPLE PROPERTIES				
	Gas Composition				
	Cl		ppm		ppm
	C2		ppm		ppm
	C3		ppm		ppm
	TC4/nC4		ppm		ppm
	C5		ppm		ppm
	C6+		ppm .	<del> </del>	ppm
	CO2/H2S		ppm	A 5 7 6	bbw
<u> </u>	Properties	API@	deg C	API@	deg C
	Colour			·	<del></del>
	Fluorescence				
le t	GOR	<u> </u>			
late	GOR er Properties	1 660 obm m	@ 21 dog C	2 710 @	dog C
Vate	GOR er Properties Resistivity	1.660 ohm-m		2.710 @	
Vato	GOR er Properties Resistivity NaCl Equivalent	3800	ppm	2400	) ppm
Vate	GOR er Properties Resistivity NaCl Equivalent Cl-titrated	3800 4,500	ppm l	2400 5 <b>,</b> 00	0 ppm 00 ppm
Vate	GOR er Properties Resistivity NaCl Equivalent Cl-titrated Tritium	3800 4,500 In: 3210 DPN	ppm ppm 1 Rec: 492 DPM	2400 5,00 Rec: 295	D ppm DPM DPM
	GOR er Properties Resistivity NaCl Equivalent Cl-titrated Tritium Est Water Type	3800 4,500	ppm ppm 1 Rec: 492 DPM	2400 5 <b>,</b> 00	D ppm DPM DPM
	GOR er Properties Resistivity NaCl Equivalent Cl-titrated Tritium Est Water Type Filtrate Properties	3800 4,500 In: 3210 DPN Formation V	ppm ppm 1 Rec: 492 DPM Vater	2400 5,00 Rec: 295 Formation W	D ppm DO ppm DPM Water
	GOR er Properties Resistivity NaCl Equivalent Cl-titrated Tritium Est Water Type Filtrate Properties Resistivity	3800 4,500 In: 3210 DPN Formation V	ppm ppm 4 Rec: 492 DPM Water n @ 16 deg C	2400 5,00 Rec: 295 Formation V	D ppm DD ppm DPM Vater  @ 16 deg
	GOR er Properties Resistivity NaCl Equivalent Cl-titrated Tritium Est Water Type Filtrate Properties Resistivity NaCl Equivalent	3800 4,500 In: 3210 DPN Formation V .295 ohm-n 25,000	ppm ppm 1 Rec: 492 DPM Water n @ 16 deg C ppm	2400 5,00 Rec: 295 Formation V .295 ohm-m 25,000	DO ppm DPM Water  @ 16 deg
/lud	GOR er Properties Resistivity NaCl Equivalent Cl-titrated Tritium Est Water Type Filtrate Properties Resistivity NaCl Equivalent Cl-titrated	3800 4,500 In: 3210 DPN Formation V	ppm ppm 4 Rec: 492 DPM Water n @ 16 deg C	2400 5,00 Rec: 295 Formation V	D ppm DD ppm DPM Vater  @ 16 deg
fud	GOR er Properties Resistivity NaCl Equivalent Cl-titrated Tritium Est Water Type Filtrate Properties Resistivity NaCl Equivalent Cl-titrated ibration	3800 4,500 In: 3210 DPN Formation V .295 ohm-n 25,000	ppm ppm 1 Rec: 492 DPM Water n @ 16 deg C ppm	2400 5,00 Rec: 295 Formation V .295 ohm-m 25,000	D ppm DDPM Vater  @ 16 deg ppm
<b>fud</b>	GOR er Properties Resistivity NaCl Equivalent Cl-titrated Tritium Est Water Type Filtrate Properties Resistivity NaCl Equivalent Cl-titrated ibration Calibration Press.	3800 4,500 In: 3210 DPN Formation V .295 ohm-n 25,000 17,000	ppm ppm 1 Rec: 492 DPM Water n @ 16 deg C ppm	2400 5,00 Rec: 295 Formation V .295 ohm-m 25,000	D ppm DDPM Vater  @ 16 deg ppm
Mud	GOR er Properties Resistivity NaCl Equivalent Cl-titrated Tritium Est Water Type Filtrate Properties Resistivity NaCl Equivalent Cl-titrated ibration Calibration Press. Calibration Temp.	3800 4,500 In: 3210 DPN Formation V .295 ohm-n 25,000	ppm ppm 1 Rec: 492 DPM Water n @ 16 deg C ppm	2400 5,00 Rec: 295 Formation V .295 ohm-m 25,000	D ppm DDPM Nater  @ 16 deg
Mud	GOR er Properties Resistivity NaCl Equivalent Cl-titrated Tritium Est Water Type Filtrate Properties Resistivity NaCl Equivalent Cl-titrated ibration Calibration Press. Calibration Temp. Hewlett Packard No.	3800 4,500 In: 3210 DPN Formation V .295 ohm-n 25,000 17,000	ppm ppm 4 Rec: 492 DPM Vater n @ 16 deg C ppm ppm	2400 5,00 Rec: 295 Formation V .295 ohm-m 25,000 17,000	D ppm DDPM Vater  @ 16 deg   ppm ppm
Mud	GOR er Properties Resistivity NaCl Equivalent Cl-titrated Tritium Est Water Type Filtrate Properties Resistivity NaCl Equivalent Cl-titrated ibration Calibration Press. Calibration Temp. Hewlett Packard No. Mud Weight	3800 4,500 In: 3210 DPN Formation V .295 ohm-n 25,000 17,000	ppm ppm ppm 4 Rec: 492 DPM Vater  1 @ 16 deg C ppm ppm ppm	2400 5,00 Rec: 295 Formation V .295 ohm-m 25,000 17,000	D ppm DDPM Vater  @ 16 deg   ppm ppm ppm
fud	GOR er Properties Resistivity NaCl Equivalent Cl-titrated Tritium Est Water Type Filtrate Properties Resistivity NaCl Equivalent Cl-titrated ibration Calibration Press. Calibration Temp. Hewlett Packard No.	3800 4,500 In: 3210 DPN Formation V .295 ohm-n 25,000 17,000 64	ppm ppm 4 Rec: 492 DPM Vater n @ 16 deg C ppm ppm	2400 5,00 Rec: 295 Formation V .295 ohm-m 25,000 17,000	D ppm DDPM Vater  @ 16 deg ppm ppm

Well : Whiptail-lA

OBSERVER : Jeff Roche

DATE : 19 August 1985 RUN NO. : Five

. OCT NOCHE		<del></del>	• 12 7.00	_			
	CHAMBER 1 (22.7 lit.)				CHAMBER 2 (10.4 lit.)		
SEAT NO.	5/5 5/6 5/7				T		
EPTH	1154.0	1154.2	2 115	8.0	1158.0		
N. RECORDING TIMES							
Tool Set	0146	0157	020				
Pretest Open	0147	0158	020	2			
Time Open	Ţ			4			
Chamber Open			020		0303		
Chamber Full			025		0322		
Fill Time			4.		19		
Start Build Up			025		0322		
Finish Build Up			030		0324		
Build Up Time			<del>-</del>	9	2		
Seal Chamber			030	2	0325		
Tool Retract	0154				0326		
Total Time			60 mir	ns.	23		
. SAMPLE PRESSURE							
IHP	1932	1932	1939 ps	sia		psig	
ĪSIP	<u> </u>		1617		1622	psig	
Initial Flowing Press.	i		72	<del>j</del>	31	psig	
Final Flowing Press.	<del>i                                     </del>	-	502	<del></del>	525	psig	
Sampling Press. Range	<del>i</del>		430	<del></del>	494	psig	
FSIP	· · · · · · · · · · · · · · · · · · ·		1622	<del></del>	1623	psig psig	
FHP	<del>i</del>	,		<del></del>	1939	psig psig	
Form.Press.(Horner)	1			<del></del>		psig	
. TEMPERATURE	<del> </del>	<del></del>		<del></del>		hora	
	<u> </u>			<del></del>			
Depth Tool Reached	<del> </del>		m dog	<del></del>	<del></del>	M dec	
Max. Rec. Temp	   07 05/27	<del>+</del>	deg			deg	
Time Circ. Stopped	23.25/17	LN	hrs.			hrs.	
Time since Circ.	26.5	<del></del>	hrs.			hrs.	
Form.Temp.(Horner)	<u> </u>		deg	<u> </u>	<del></del>	psig	
• SAMPLE RECOVERY			·	<u> </u>			
Surface Pressure	<u> </u>	650	psi			psig	
Amt Gas	]	0.85	cu 1			lit.	
Amt Oil			lit			lit.	
Amt Water			lit			lit.	
Amt Others (Filtrate)		22.00	lit		10.2	O lit.	
. SAMPLE PROPERTIES							
Gas Composition							
Cl	NOT END	UGH	ppm	1		ppm	
C2	GAS		ppm			ppm	
C3	I TO	<del></del>	ppm			ppm	
TC4/nC4	MEASURI	Ē	ppm		x	ppm	
C5	l		ppm			ppm	
C6+	<u></u>	<del></del>	ppm			ppm	
C02/H2S	<u> </u>	······································	ppm			ppm	
il Properties	Δ	PI@	deg	<del>c i</del>	API@		
Colour	71	16	acg	<del></del>	- N Te	<u>ucg</u>	
			<del> </del>	- 1		<u> </u>	
Fluorescence GOR	<u>'</u>					<del></del>	
	1	· · ·	<del> </del>	<u> </u>			
ater Properties	1 300 -		10 ==	<del>_                                    </del>	2 ZE	@ 10 d==	
Resistivity	1.300 ol				2.35 ohm-m		
NaCl Equivalent	5,000		ppm		3,500	ppm	
Cl-titrated	5,50		ppm		5,000	ppm	
Tritium	In: 3098			JLM	Rec: 532	DPM	
Est Water Type	Formatio	on Wate	<u>:</u>		Formation 1	water	
ud Filtrate Properties			<del></del>			<del></del>	
Resistivity	.295 ohi				ohm@		
NaCl Equivalent	25,00		ppm			ppm	
Cl-titrated	17,00	0	ppm			ppm	
alibration							
Calibration Press.	l						
Calibration Temp.							
Hewlett Packard No.							
Mud Weight	9	.8	ppg	<del>i</del> -		ppg	
Calc.Hydrostatic		.9	ppg	<del></del> -	<del></del>	ppg	
Chokesize/Probe Type			Martinea		1 x :03	O"/Martine	
EMARKS	Tight (5/				V. Clean		
	Min Flow	Min	Flow	1			

Well : Whiptail-IA

OBSERVER : Jeff Roche DATE : 19 August 1985 RUN NO. : Six

	<del></del>		<del></del>	_		
		CHAMBER	₹ 1 (22.7		CHAMBER 2 ()	LO.4 lit.)
ISEA	T NO.	6/8	6/9	6/10	6/10	
DEP	TH	1497.5	1497.0	1497.0	1497.0	
A.	RECORDING TIMES	T				
i —	Tool Set	0528	0535	0540		<del></del>
<u> </u>	Pretest Open	0530		0540		
¦	Time Open	<del></del>		1		
¦	Chamber Open	0533	<del></del>	0541	0546	<del></del>
¦	Chamber Full	1 0000		0546	0548	
<u> </u>	Fill Time	<del> </del>		5	2	<del></del>
¦		<u> </u>			0546	
<u> </u>	Start Build Up	1		0546	<u> </u>	<del></del>
ļ	Finish Build Up	<u> </u>		0546	0548	<del></del>
<u> </u>	Build Up Time	<u> </u>			2	<del> </del>
	Seal Chamber				05:52	
<u> </u>	Tool Retract				05:55	
	Total Time		min	S		
B.	SAMPLE PRESSURE					
[	IHP	2517	2515	2516		psig
	ISIP	2121		2122	2118	psig
	Initial Flowing Press.	2500		2110	1182	psig
	Final Flowing Press.	[		2112	2120	psig
i	Sampling Press. Range	Ī T		· · · · ·	1000	psig
i	FSIP			2118	2120	psig
i	FHP	İ	·- · · · · · · · · · · · · · · · · · ·	<del>_</del> _	0514	psig
i	Form.Press.(Horner)	<del>}</del>			<del> </del>	psig
C.	TEMPERATURE		<del></del>			
٠	Depth Tool Reached			m		m
<u> </u>		<del> </del>	<del></del>	deg C		
¦	Max. Rec. Temp	07 05/174	-1-		· · · · · · · · · · · · · · · · · · ·	deg C
<u> </u>	Time Circ. Stopped	23.25/17t	<u>cn</u>	hrs.		hrs.
ļ	Time since Circ.	30		hrs.	<del></del>	hrs.
<u> </u>	Form.Temp.(Horner)	<u> </u>	<del> </del>	deg C	·	psig
D.	SAMPLE RECOVERY					
	Surface Pressure	150		psig	-	psig
i	Amt Gas	-		lit.	-	lit.
	Amt Oil	_		lit	-	lit.
l	Amt Water	20.50		lit	9.00	lit.
	Amt Others (Filtrate)	_		lit.		lit.
E.	SAMPLE PROPERTIES	ĺ	<del>·</del>		<del></del>	
	Gas Composition			· · · · · · · · · · · · · · · · · · ·		
ĺ	Cl	İ		ppm 1		ppm
	C2		<del></del>	ppm		ppm
	<u> </u>	<u> </u>		ppm	· · · · · · · · · · · · · · · · · · ·	ppm
	TC4/nC4	·				
	C5	, [	<del></del>	ppm	· · · · · · · · · · · · · · · · · · ·	ppm
	C6+	·		ppm i		ppm
				ppm		ppm
<u> </u>	CO2/H2S	<u> </u>	T6	ppm l	1076	ppm
OIT	Properties	AF	PI@	deg C	API@	deg C
	Colour	<u> </u>				
	Fluorescence			.	<del> </del>	·····
	GOR					
Wate	er Properties					
	Resistivity	.613 c	ohm-m @ 20		1.700 ohm-m @	
	NaCl Equivalent	10,00	00	ppm	3 <b>,</b> 700	) ppm
	Cl-titrated	10,00	00	ppm	4,500	) ppm
	Tritium	In: 3200	DPM Rec:	1594 DPM	Rec: 400	) dpm
	Est Water Type		Formation (		Formation wa	
Mud	Filtrate Properties	]		İ		
	Resistivity	.295 ohm-m	n @ 16	deg C	ohm@	deg C
	NaCl Equivalent	25,00		ppm		ppm
	Cl-titrated	27,00		ppm		ppm
Cal	ibration		· <del></del>	<u> </u>		
<u></u>	Calibration Press.			nom l	<del></del>	
	Calibration Temp.			ppm l		ppm
	Hewlett Packard No.			nna		- nna
			<u> </u>	ppg	0.0	ppg
	Mud Weight	9.8	<u> </u>	ppg I	9.8	ppg
	Calc.Hydrostatic		0701.44		4	
	Chokesize/Probe Type		030"/Mart	.ıneau	1 x .U3U"	/Martineau
KEMA	ARKS	Seal	No C1	!		
	<u> </u>	Failure	Seal	ļ		
				1		

Well : Whiptail-lA

OBSERVER : Jeff Roche DATE : 19 August 1985 RUN NO. : Seven

SEAT NO.		22 lit.)	CHAMBER 2 (10.	T 110.
	7/11 7/12	7/13		
DEPTH	1275.5 1276.5 1			
A. RECORDING TIMES	12//1/ 12/01/ 2			
Tool Set	0753 0758	0805		<del></del>
Pretest Open	0754 0800	0805		
Time Open				
Chamber Open				
Chamber Full				
Fill Time		mins.	mins.	
Start Build ∪p			•	
Finish Build Up				
Build Up Time			mins.	
Seal Chamber				
Tool Retract				
Total Time		mins.	mins.	
B. SAMPLE PRESSURE	1 0177 0177	01/1		
IHP	2137 2137	2141 psig		_psig
ISIP		psig	. <del> </del>	psig
Initial Flowing Pres		psig	·	psig psig
Final Flowing Press.		psig		psig
Sampling Press. Rang		psig		psig
FSIP FHP				psig
				psig
Form.Press.(Horner) C. TEMPERATURE				porg
Depth Tool Reached		m l		m
Max. Rec. Temp		deg C		deg C
Time Circ. Stopped	hrs	ueg o	hrs	ucg o
Time since Circ.	1117.2	hrs İ	1113	hrs
Form.Temp.(Horner)		1113		psig
D. SAMPLE RECOVERY	<del>-  </del>	<del></del>		porg
Surface Pressure		psig		psig
Amt Gas		cu ft	· · · · · · · · · · · · · · · ·	cu ft
Amt Oil		lit	· · · · · · · · · · · · · · · · · · ·	lit
Amt Water	<del>-  </del>	lit i		lit
Amt Others (Filtrate	<u> </u>	CC		CC
E. SAMPLE PROPERTIES				
Gas Composition		İ		
Cl	i	ppm 1		ppm
C2		ppm		ppm
C3	<u> </u>	ppm		ppm
TC4/nC4		ppm	· · · · · · · · · · · · · · · · · · ·	ppm
C5		ppm		ppm
C6+		ppm		ppm
CO2/H2S		%/ppm		%/ppm
Oil Properties	API@	deg C	API@	deg C
Colour	i i			
Fluorescence	Till the second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second	T T		<del> </del>
GOR				
Water Properties				
Resistivity	ohm@	deg C	ohm@	deg C
NaCl Equivalent		ppm		ppm
Cl-titrated		ppm		ppm
Tritium		DPM		DPM
Est. Water Type				
Mud Filtrate Properties				
Resistivity	ohm@	deg C	ohm@	deg C
NaCl Equivalent		ppm		ppm
Cl-titrated		ppm		ppm
Calibration				<u></u>
Calibration Press.		<u> </u>		
Calibration Temp.				
Hewlett Packard No.				
Mud Weight		ppg		ppg
Calc.Hydrostatic		ppg l		ppg
Chokesize/Probe Type				
REMARKS	Very tight	t l		
INCIMALVO	;,5			

Well

: Whiptail-lA

OBSERVER : J. Roche/D. Bailey DATE : 19 August 1985 RUN NO. : Seven

1		CHAMBER 1 (	(22.7 lit.)	CHAMBER 2 ()	l0.4 lit.)
SEA	T NO.	7/24		7/24	
DEP		1363.5	5	1363.5	
IA.	RECORDING TIMES				
	Tool Set	1055		<u> </u>	
	Pretest Open	1056		<u> </u>	<del></del>
<u> </u>	Time Open		nins	<u> </u>	
<u> </u>	Chamber Open	1058		1115	
<u> </u>	Chamber Full	1111		1116	
<u> </u>	Fill Time	13 n	nins	1 mi	<u>.n                                    </u>
ļ	Start Build Up Finish Build Up	1111   1114		1116 1118	
!	Build Up Time	<u>.                                    </u>	nins	1 2 mj	ne
<u> </u>	Seal Chamber	1114	тиэ	1118	.115
¦	Tool Retract		<del> </del>	1118	
<u> </u>	Total Time	<u> </u>	mins.		hrs
iB.	SAMPLE PRESSURE	<u> </u>	11121101	1	,,,,,
<u> </u>	IHP	2279	psig	<u> </u>	psig
i	ISIP	1924	psig	1919	psig
i —	Initial Flowing Press.	1095	psig	1119	psig
	Final Flowing Press.	1918	psig	1910	psig
	Sampling Press. Range	823	psig	791	psig
	FSIP	1919	psig	1920	psig
	FHP			2277	psig
	Form.Press.(Horner)			1	psig
C.	TEMPERATURE	<u> </u>		<u> </u>	
ļ	Depth Tool Reached	<u> </u>	m		<u>m</u>
<u> </u>	Max. Rec. Temp	<u> </u>	deg C	<u> </u>	deg C
<u> </u>	Time Circ. Stopped	<u> </u>	hrs.	<u> </u>	hrs.
<u> </u>	Time since Circ.		hrs.		hrs.
D.	Form.Temp.(Horner) SAMPLE RECOVERY	<u>                                     </u>	deg C	1	psig
<u> </u>  -	Surface Pressure	450	psig	_	poid
¦	Amt Gas	0.5	cu ft	<del></del>	psig lit.
¦	Amt Oil		lit		lit.
	Amt Water	22.0	Tit	10.0	lit.
i	Amt Others (Filtrate)		lit.	1 10.0	lit.
Ē.	SAMPLE PROPERTIES			<u> </u>	
i	Gas Composition		· · · · · · · · · · · · · · · · · · ·		<del> </del>
Ì	Cl	]	ppm	Ì	ppm
	C2		ppm		ppm
	C3		ppm		ppm
l	TC4/nC4		ppm		ppm
	C5		ppm		ppm
	C6+		ppm		ppm
	CO2/H2S		ppm		ppm
Oil	Properties	API@	deg C	API@	deg C
	Colour				
	Fluorescence	<u> </u>			
141 - *	GOR			<u> </u>	
wat	er Properties	 	@ 30 dag 0	l   0 710 -b	20 4 0
	Resistivity		@ 20 deg C	0.710 ohm-m @ 9000	
<b></b>	NaCl Equivalent Cl-titrated	14,000	ppm	1 7000	ppm
	Tritium I	In: 3139 DPM	ppm Rec: 160 DPM	Rec: 92	ppm DPM
	Est Water Type	Formation		Formation w	
Mud	Filtrate Properties	OTHIGOTOIT		, OTHECTOIT W	
	Resistivity	.295 ∩hm=m	0 16 deg C	ohm@	deg C
	NaCl Equivalent	25,000	ppm	. Or me	ppm
	Cl-titrated	17,000	ppm	<u> </u>	ppm
Cal	ibration		F (F 272		
	Calibration Press.			<u> </u>	
	Calibration Temp.				<del> </del>
	Hewlett Packard No.				
	Mud Weight	9.8	ppg		ppg
	Calc.Hydrostatic	9.8	ppg		ppg
	Chokesize/Probe Type	1 x .030	"/Martineau	l x .030"/	Martineau
REM	ARKS				
	ļ.				
				i	

Well : Whiptail-lA

OBSERVER : J. Roche/R. Mosley DATE : 28 August 1985 RUN NO. : Eight

,			UDED 3	7,5	7.54 \ 1	OUAMPED.	0 /10	6 7 2 ± X
ICEN	T NO.	8/25	MBER 1 8/26	8/27		8/29	2 (10.	4 lit.)
DEP		•			0 2663.7		2665.	<u> </u>
A.	RECORDING TIMES	12004.7	2000.0	2000.	0 2000.71	2007.0	2002.	<u> </u>
	Tool Set	0551	0638	0614	0645	0653	0655	
	Pretest Open	0551	0638	0614	0645	0653	0655	<del></del>
	Time Open	6		4				
	Chamber Open	0557		0618	j	<del></del>		
	Chamber Full						~ ···· •·········	
	Fill Time							
	Start Build Up							
	Finish Build Up							
	Build Up Time							······································
	Seal Chamber	0608		0630			0.450	
	Tool Retract	0609	0640	0632	0648	0654	0658	
	Total Time SAMPLE PRESSURE	<u> </u>		hrs.			<del></del>	
В.	IHP	4338	4325	4325	4320 I	4325	4325	noid
	ISIP	3796	4525	3784	psig	4323	4525	psig psig
	Initial Flowing Press.	17770	<del></del>	2704	psig i	<del> </del>	<del></del>	psig
i	Final Flowing Press.	<del> </del>		···	·····			psig
	Sampling Press. Range	İ						psig psig
	FSIP	Ī			i			psig
	FHP					· • · · · · · · · · · · · · · · · · · ·		psig
	Form.Press.(Horner)	<u> </u>						psig
C.	TEMPERATURE							
	Depth Tool Reached	2667			m			m
	Max. Rec. Temp	87.8		88.3	deg C			deg C
	Time Circ. Stopped	<u> </u>			hrs.			hrs.
	Time since Circ.				hrs.			hrs.
	Form.Temp.(Horner)				deg C			psig
D.	SAMPLE RECOVERY							
ļ	Surface Pressure				psig			psig
	Amt Gas	[ 			lit.	·		lit.
	Amt Oil	<u> </u>	<del></del>		lit			lit.
<u> </u>	Amt Water Amt Others (Filtrate)	<u> </u>	<del></del>	<del> </del>	lit			lit.
E.	SAMPLE PROPERTIES	<u> </u>			lit.	~		lit.
<u></u>	Gas Composition	<u> </u>						
	Cl	i İ			nnm			nnm
	C2	!			ppm (	<del></del>		ppm
	<u>C3</u>				ppm I			ppm
	TC4/nC4	<u> </u>			ppm			ppm
	C5		· · · · · · · · · · · · · · · · · · ·		ppm			ppm
	C6+				ppm	- · · · · · · · · · · · · · · · · · · ·	·	ppm
	CO2/H2S	<u> </u>			ppm			ppm
Oil	Properties		API@		deg C	API	<u> </u>	deg C
	Colour	l						
	Fluorescence							
	GOR							
Wate	er Properties							
	Resistivity		@		deg C		<u>@</u>	deg C
	NaCl Equivalent				ppm i	<del></del>		ppm
	Cl-titrated				ppm	<del></del>		ppm
	Tritium  Fot Water Type				DPM		<del></del> .	DPM
M: :~!	Est Water Type	<u> </u>					<del></del>	
MUU	Filtrate Properties Resistivity		ohm@	···	dog C	-L	<u>a</u>	dog C
	NaCl Equivalent	<u> </u>	UI IIII		deg C	ohm	ia ia	deg C
	Cl-titrated		<del></del>		ppm	<del></del>		ppm
Cali	bration	<u> </u>		<del></del>	ppm I			ppm
~a⊥.	Calibration Press.			<del></del>				
	Calibration Temp.			<del> </del>	<del></del>			
	Hewlett Packard No.				<del></del>	<del></del>	<del></del>	
	Mud Weight				ppg		<del></del>	ppg
	Calc.Hydrostatic				ppg			ppg
	Chokesize ·				<u> </u>		<del>-</del>	rr 3
REM/		Tight	tests		T T			· · · · · · · · · · · · · · · · · · ·
	I	-			I			

# RFT SAMPLE TEST REPORT

Well : Whiptail 1A

OBSERVER : Jeff Roche/Rob Mosley DATE : 28 August 1985 RUN NO. : Eight

;		CHAMPED 1 //E	/ 12± \	CHAMPED 2 /10	/ı 12± \
ICEN	T NO.	CHAMBER 1 (45.	.4 lit.)   32 8/33	CHAMBER 2 (10,	.4 IIT.)
IDEP	· · · · · · · · · · · · · · · · · ·	2650.0 2649.5 264			
A.	RECORDING TIMES	12000.0 2040.0 20-	+0.5 2051.01		
1	Tool Set	0705 0712 072	28 0737	····	
i	Pretest Open	0705 0712 072			<del></del>
i —	Time Open	3	3		
i —	Chamber Open	0715	0740		
	Chamber Full				
	Fill Time				
	Start Build Up				
<u> </u>	Finish Build Up			· · · · · · · · · · · · · · · · · · ·	
ļ	Build Up Time	6710	075	<del>,</del>	
ļ	Seal Chamber	0719 0707 0724 073	0756   31 0758		
<u> </u>	Tool Retract Total Time	0707 0724 073			
iB.	SAMPLE PRESSURE	I	hrs.		
<u> </u>	IHP	4301 4300 429	95 4302		psig
¦	ISIP	3754	3755		psig psig
¦	Initial Flowing Press.	1 40	20		psig
<u> </u>	Final Flowing Press.	40	138		psig
<u> </u>	Sampling Press. Range	<u>,                                     </u>		· · · · · · · · · · · · · · · · · · ·	psig
<u> </u>	FSIP FSIP	<del> </del>	<del></del>	<del></del>	psig
i-	FHP				psig
i	Form.Press.(Horner)				psig
ic.	TEMPERATURE		<del></del>	<del></del>	
i	Depth Tool Reached	2667	m		m
İ	Max. Rec. Temp	88.3	deg C		deg C
j	Time Circ. Stopped	12.00/27th	hrs.		hrs.
	Time since Circ.	19.5	hrs.		hrs.
	Form.Temp.(Horner)		deg C		psig
ID.	SAMPLE RECOVERY				
	Surface Pressure		psig		psig
<u> </u>	Amt Gas	0.8	cu ft	· · · · · · · · · · · · · · · · · · ·	lit.
<u> </u>	Amt Oil		lit		lit.
<u> </u>	Amt Water	20.00	lit	<del></del>	lit.
ļ	Amt Others (Filtrate)	<u> </u>	lit.		lit.
E.	SAMPLE PROPERTIES	<u> </u>	<u></u>		
1	Gas Composition Cl	NOT ENOUGH	nom I		nnm
i	<u>C2</u>	GAS	ppm		ppm
<u> </u>	C3	TO	ppm		ppm
<u> </u>	TC4/nC4	MEASURE	ppm		ppm
i	C5	, , , , , , , , , , , , , , , , , , , ,	ppm l		ppm
i	C6+		ppm		ppm
i	C02/H2S		ppm		ppm
Oil	Properties	API@	deg C	API@	deg C
1	Colour		<del>-</del>		
	Fluorescence		i	<del> </del>	
	GOR				
Wate	er Properties				
	Resistivity	.23 ohm-m @	16 deg C	@	deg C
	NaCl Equivalent	30,000	ppm		ppm
	Cl-titrated	18,000	ppm		ppm
	Tritium	In: 3250 DPM Rec	: 3020 DPM		ppm
	Est Water Type	Filtrate			
Mud	Filtrate Properties	010			<del>,</del>
<u> </u>	Resistivity	.210 ohm-m @ 18		ohm@	deg C
<b> </b>	NaCl Equivalent	35,000	ppm		ppm
1001	Cl-titrated Lbration	18,000	ppm		ppm
loar.	Calibration Press.		<u>I</u>	<del></del>	<del></del>
¦	Calibration Temp.			<del>~ · · · · · · · · · · · · · · · · · · ·</del>	
<u> </u>	Hewlett Packard No.		<del></del>		<del></del>
i	Mud Weight	9.5	ppg		ppg
i	Calc.Hydrostatic	9.5	ppg	<del>- · · · · · · · · · · · · · · · · · · ·</del>	ppg
i	Cokesize/Probe Type	.030"/Marti			<u> </u>
REM.					
1		Tight	j	Not opened	
_		1 -	İ	•	

# RFT SAMPLE TEST REPORT

Well : Whiptail-lA

OBSERVER : Jeff Roche/Rob Mosely DATE : 28 August 1985 RUN NO. : Nine

ı ———		CHAN	BER 1 (	45.4	lit.)	CHAMBER	2 (10.	4 lit.)
SEA	r No.	9/39	9/40	9/41	<del></del>		9/41	
DEPT		2665.0	2665.0	2664.	5		2664.5	
A.	RECORDING TIMES							
	Tool Set	1336	1340	1349				
	Pretest Open	1336	1340	1349				
	Time Open							
	Chamber Open			1355			1447	
[	Chamber Full							
i	Fill Time							
<u> </u>	Start Build Up		****					
İ	Finish Build Up							
j	Build Up Time							
	Seal Chamber			1443			1506	
Ì	Tool Retract	1338	1343	-			1508	
	Total Time			mins	•			
B.	SAMPLE PRESSURE							
i	IHP	4341	4344	4342	psia			psia
i	ISIP	4344	4343	3801			3771	psia
i	Initial Flowing Press.			33			50	psia
i	Final Flowing Press.			65			65	psia
i	Sampling Press. Range				· · · · · · · · · · · · ·		<del></del>	psia
i	FSIP	[		3771			3755	psia
i	FHP	i i	<del></del>				4339	psia
i	Form.Press.(Horner)	<u> </u>						psia
ic.	TEMPERATURE	<del>i</del>			<del>-</del>			
i <del>~</del>	Depth Tool Reached				m		<del></del>	m
¦	Max. Rec. Temp	<u> </u>			deg C			deg C
¦	Time Circ. Stopped	<del></del>			hrs.			hrs.
<u> </u>	Time since Circ.	<u> </u>			hrs.			hrs.
	Form. Temp. (Horner)				deg C	<u> </u>		psig
D.	SAMPLE RECOVERY	<u> </u>			ucg c		<del></del>	porg
<del>   </del>	Surface Pressure	1 	Ω		psig		0	psig
<u> </u>		<b>;</b> 	0.6		cu ft	Trace		cu ft
<u> </u>	Amt Gas	<u> </u>	0.0		lit	11ace		lit.
<u> </u>	Amt Oil	<u> </u>	7.30			 	5.0	lit.
<u> </u>	Amt Water	1	7.50		lit lit.		• 0	lit.
<u> </u>	Amt Others (Filtrate)	<u> </u>			III.		<del></del>	<u> </u>
E.	SAMPLE PROPERTIES	<u> </u>				<del></del>		<del></del>
ļ	Gas Composition	[ ] T				   1472	277	
<u> </u>	Cl		icient		ppm	1473		ppm
<u> </u>	C2	ı sar	nple	<del> </del>	ppm		28	ppm
<u> </u>	C3	<u> </u>			ppm		591 140	ppm
!	TC4/nC4	<u> </u>			ppm		249	ppm
	C5	<u> </u>			ppm		80	ppm
	C6+	<u> </u>			ppm		30	ppm
	CO2/H2S				ppm		IL	ppm
<u> 0il</u>	Properties	<u> </u>	API@		deg C	AP	I@	deg C
	Colour							<del></del>
	Fluorescence	1						
	GOR							
Wate	er Properties							
	Resistivity	(	0.265 @	16.5	deg C	0.268	@ 16.5	
	NaCl Equivalent				ppm			ppm
	Cl-titrated		17,500		ppm	18,000	1	ppm
	Tritium				2801 DPM	Rec: 2692		DPM
1	Est Water Type	l F	iltrate	?		Fil	trate	
Mud	Properties	[						
1	Resistivity	0.210	ohm-m @	18.5	deg C	0.210 ohm-	m @ 18.	5 deg C
1	NaCl Equivalent		35,000		ppm		************	ppm
	Cl-titrated	<u> </u>	18,000		ppm	18,00	0	ppm
Cal	ibration					<u> </u>		
l	Calibration Press.	<u> </u>			- · · · · · · · · · · · · · · · · · · ·	<u> </u>		
i	Calibration Temp.	Ī						
i	Hewlett Packard No.	İ			<del></del>			
i <del></del>	Mud Weight	<u> </u>	9.5		ppg			ppg
i	Calc.Hydrostatic	<u>.</u>	9.6		ppg	<del> </del>		ppg
	Chokesize/Probe Type	<del>i.                                      </del>		ongno		r <del></del> /	Longno	
RFM/	ARKS	HP Gau	ide , ,	-0119110		<del>r</del>		
,, <u>,</u>		i ada	-9~			i		
ı İ						i		

# APPENDIX 6

# APPENDIX 6

Velocity Survey Report

# VELOCITY SURVEY REPORT

CONTENT	<u>S</u>	PAGE NO
1.	Marine Velocity Survey Summary.	1
2.	Field Report from Esso Representative.	2
3.	Schlumberger Processing Report.	3
4.	Schlumberger Field Report.	11
5.	Gun Geometry Sketch.	12
6.	Check Shot Data - Observed and Corrected.	13

# ENCLOSURES

- 1. Schlumberger Seismic Calibration Log; Sonic Drift Curve, Adjusted Continuous Velocity Log and Schlumberger Time-Depth Curve.
- Schlumberger Raw and Stacked Shots.
- 3. Schlumberger "Geogram" (Synthetic Seismogram).
- 4. Esso Time-Depth Curve.

2061L/50

## 1. MARINE VELOCITY SURVEY SUMMARY

WELL:

WHIPTAIL-1A

TYPE:

Wildcat

BASIN:

Gippsland

LICENCE:

VIC/L1

DATE OF SURVEY:

August 28, 1985.

CONTRACTOR:

Schlumberger

RECORDED BY:

D. J. Dawson (Schlumberger)

WITNESSED BY:

A. G. Barrett (Esso)

WELLHEAD CO-ORDINATES:

38° 19' 30.351" S 147° 31' 9.587" E X = 545,394.04 mE Y = 5,757,971.49 mN

RIG:

Southern Cross

WATER DEPTH:

39.0 m

K.B. ELEVATION:

21.0 m AMSL

D.F. ELEVATION:

20.7 m AMSL

T.D. WHEN SHOT:

2821 m (driller) 2817.5 m (logger)

CASING DEPTHS:

20" @ 182m, 13 3/8" @ 782m

**ENERGY SOURCE:** 

Bolt Airgun, 200 cu. in.

SOURCE DEPTH:

9.1m below MSL

SOURCE OFFSET:

37 m

SOURCE AZIMUTH:

50°

SOURCE SENSOR:

Accelerometer

DOWNHOLE GEOPHONE:

Geospace HS-1

RECORDING INSTRUMENT:

Schlumberger computerised service unit (CSU)

2061L/51

#### 2. FIELD REPORT FROM ESSO REPRESENTATIVE

#### WHIPTAIL-1A VELOCITY SURVEY

The first shot was attempted at 1756 hrs. It was unsuccessful because of a fatal CPU error. Another shot was tried at 1803 hrs and another fatal error occurred. The engineer then changed the software from version 28.2 (which is the commercial release of the field test version 28.15) and replaced it with version 28.15.

The next shot attempt was also unsuccessful. A tap on the gun air supply was found to be disconnected.

After the next shot, the the engineer noticed that the polarity of the moonpool hydrophone was reversed. This was remedied and the first valid shot was taken at 1829 hrs.

The first seven valid shots were used to determine the gun offset.

A gamma-ray correlation was then run over the interval 1148m to 1175m. It showed that the depth recorder was reading 2m shallow. A correction was made for this discrepancy.

One more valid shot was then fired before another fatal CPU error occurred. At this stage the engineer mounted a new data tape as he thought that this may have been the problem. He also changed to another CPU and reloaded the WST program.

Shots were fired at 1126m on the way to TD to compare with shots fired on the way out. (The latter shots showed a difference of 2.4 msec.)

Another gamma-ray correlation was performed at TD. It showed that no further correction was required.

Again after one valid shot at TD a fatal CPU error occurred. This time the engineer thought the problem may be related to switching between the gamma-ray and WST programs. He referred to the operator's printout for the Snapper-5 WST and found exactly the same problem had occurred. After setting up the WST program yet again the survey proceeded smoothly.

The lowest level of data acquired was at 2815m. Noise at this level did not present a problem. In fact, the hole presented very few noise problems except at the highest level attempted, 200m. Data were acquired at this level but are probably unreliable.

Four shots were recorded at 1530m. All four were of only fair quality, consequently the tool was moved up to 1525m, where three good shots were recorded.

The last shot was fired at 2309 hrs and the tool was out of the hole at 2326 hrs and rigged down at 2330 hrs. The tool zero could not be checked as the drillers were working on the rig compensators as the tool came out of the hole but it is believed that the discrepancy was less than one metre. In all nineteen levels of data were acquired from 104 shots.

Weather conditions at the time of the survey were:

Wind 20 knots dir  $260^{\circ}$  Swell 6 ft dir  $260^{\circ}$  period 6s Wave ht 1 ft dir  $260^{\circ}$  period 1s Current 0.4 knots dir  $080^{\circ}$  Generally overcast.

A. G. Barrett.

#### 3. SCHLUMBERGER PROCESSING REPORT

## 1.0 INTRODUCTION

A velocity check shot survey was conducted in the WHIPTAIL #1A well on 28-August-1985. Nineteen levels from 200metres to 2815metres below DF were shot using an airgun source. Seventeen of these levels have been used in the calibration of the sonic log.

The shot times and calibrated sonic times have been corrected to a nominal Mean Sea Level Datum.

# 2.0 DATA ACQUISITION

Table 1: Field Equipment and Survey Paramters

Elevation SRD	Mean Sea Level
Elevation KB	21.0metres AMSL
Elevation DF	20.7metres AMSL
Elevation GL	-39.0metres AMSL
No. of Levels	19
Well Deviation	Nil
Total Depth	2815metres below DF
Energy Source	Bolt airgun,200cu.in.
Source Offset	37metres
Source Depth	9.1metres below MSL
Source Azimuth	50°
Reference Sensor	Accelerometer
Sensor Offset	37metres
Sensor Depth	9.1metres below MSL
Downhole Geophone	Geospace HS-1
Downtold Geophem	High Temp. (350° F)
	Coil Resist. $225\Omega \pm 10\%$
	Natural Freq. $8 - 12Hz$
	Sensitivity 0.45V/in/sec
•	Maximum tilt angle 60°
	Waximum one angle oo

Recording was made on the Schlumberger Computerized Service Unit (CSU) using LIS format.

### 2.1 Survey Details

The survey was shot as a standard offshore velocity survey. A moonpool hydrophone was positioned close to the wellhead and has been used to calculate the gun offset position. No major problems were noted during the survey.

## 3.0 CHECK SHOT DATA

A total of 19 check levels were shot during the survey. The stacked data at 200 metres below DF is distorted by noise, probably due to casing arrivals. After filtering with a 10 - 80 Hz bandpass filter the first arrival is still significantly distorted and hence has been omitted from the computations and calibration of the sonic log. The stacked data at 1530 metres below DF is also slightly distorted. This level is very close to the adjacent level at 1525 metres below DF and hence has also been omitted from the computations and calibration of the sonic log.

The level at 1126 metres below DF was shot both going into and coming out of the well. Transit times from both sets of data were similar but only the data from the shots shot coming out of the well has been used in the final stack.

A plot of the stacked check shot data is displayed as Plot 7 of the Raw and Stacked Shots.

Table 2

Level Depth (m below DF)	Stacked Shots	Rejected Shots	Quality	Comments
200	4	1	Poor	Distorted / Omitted
390	3	0	Good	•
688	3	0	Good	
800	3	3	$\mathbf{Good}$	
967	3	0	Good	
1126	7	8	$\operatorname{Good}$	
1157	4	0	$\operatorname{Good}$	
1203	4	0	$\mathbf{Good}$	
1379	5	2	$\operatorname{Good}$	
1525	3	0	$\operatorname{Good}$	•
1530	3	1	Fair	Omitted
1687	4	0	Good	
1867	3	0	Good	
2002	3	1	$\operatorname{Good}$	
2166	3	0	Good	
2312	4	1	$\operatorname{Good}$	
2456	3	0	$\operatorname{Good}$	
2619	3	0	$\operatorname{Good}$	
2815	4	<b>3</b>	$\operatorname{Good}$	

# 4.0 SONIC CALIBRATION

A 'drift' curve is obtained using the sonic log and the vertical check level times. The term 'drift' is defined as the seismic time (from check shots) minus the sonic time (from integration of edited sonic). Commonly the word 'drift' is used to identify the above difference, or to identify the gradient of drift verses increasing depth, or to identify a difference of drift between two levels.

The gradient of drift, that is the slope of the drift curve, can be negative or positive.

For a negative drift  $\frac{\Delta drift}{\Delta depth}$  < 0, the sonic time is greater than the seismic time over a certain section of the log.

For a positive drift  $\frac{\Delta drift}{\Delta depth} > 0$ , the sonic time is less than the seismic time over a certain section of the log.

The drift curve, between two levels, is then an indication of the error on the integrated sonic or an indication of the amount of correction required on the sonic to have the TTI of the corrected sonic match the check shot times.

Two methods of correction to the sonic log are used.

- 1. Uniform or block shift This method applies a uniform correction to all the sonic values over the interval. This uniform correction is applied in the case of positive drift and is the average correction represented by the drift curve gradient expressed in  $\mu sec/m$ .
- 2.  $\Delta T$  Minimum In the case of negative drift a second method is used, called  $\Delta t$  minimum. This applies a differential correction to the sonic log, where it is assumed that the greatest amount of transit time error is caused by the lower velocity sections of the log. Over a given interval the method will correct only  $\Delta t$  values which are higher than a threshold, the  $\Delta t_{min}$ . Values of  $\Delta t$  which are lower than the threshold are not corrected. The correction is a reduction of the excess of  $\Delta t$  over  $\Delta t_{min}$ ,  $\Delta t \Delta t_{min}$ .

 $\Delta t - \Delta t_{min}$  is reduced through multiplication by a reduction coefficient which remains constant over the interval. This reduction coefficient, named G, can be be defined as:

$$G = 1 + \frac{drift}{\int (\Delta t - \Delta t_{min})dZ}$$

Where drift is the drift over the interval to be corrected and the value  $\int (\Delta t - \Delta t_{min}) dZ$  is the time difference between the integrals of the two curves  $\Delta t$  and  $\Delta t_{min}$ , only over the intervals where  $\Delta t > \Delta t_{min}$ .

Hence the corrected sonic:  $\Delta t = G(\Delta t - \Delta t_{min}) + \Delta t_{min}$ .

# 5.0 SONIC CALIBRATION PROCESSING

### 5.1 Open Hole Logs

Both the sonic and density logs used have been edited prior to input into the WST chain.

:

Density data was only available below 1100 metres below DF. Above this depth a constant density reading of 2.21g/cc has been imposed. The density log has been patched over intervals of borehole washout, notably, 2041 - 2043, 2156 - 2163, 2203 - 2205, 2217 - 2219, 2370 - 2375, 2389 - 2391, 2411 - 2413, 2642 - 2647, 2690 - 2692, 2696.5 - 2698.5, 2713 - 2720 and 2730 - 2735 metres below DF. A number of smaller zones have also been patched.

Density log interval

1100 to 2815 metres below DF

Sonic log interval

183 to 2815 metres below DF

#### 5.2 Source Offset

The moonpool hydrophone was positioned 4.42 metres from the wellhead. This hydrophone was recording at each shot and an average transit time from gun to moonpool hydrophone of 22msec was measured. Using this time and a water velocity of 1480m/sec an offset of 32.56metres was calculated between gun and moonpool hydrophone. Hence the offset of the gun from the wellhead was calculated as 32.56 + 4.42 = 36.98metres

#### 5.3 Correction to Datum

Scismic Reference Datum (SRD) is at Mean Sea Level. The airgun was positioned 9.1 metres below MSL. Using a water velocity of 1480 metres/sec a correction of 6.15 msecs has been applied vertically between gun and datum.

### 5.4 Imposed Shots and Velocity Modelling

Two imposed shots were used in addition to the checkshot data to calibrate the sonic log.

- 1. Sea floor: depth 59.7 metres below DF, water velocity 1480 metres/sec
- 2. Top sonic: depth 183.03 metres below DF. The velocities above and below this level were chosen to maintain a linear sonic drift curve from this level down to lower check levels.

The velocity model used is displayed below. Depths stated are referenced to metres below Derrick Floor and metres below Mean Sea Level respectively.

SRD		20.7 / 0.0metres
	1480metres/sec	
Seabed		59.7 / 39metres
	1970metres/sec	
Top of sonic		183.03 / 162.33 metres

## 5.5 Sonic Calibration Results

The top of the sonic log (183.03 metres below DF) is chosen as the origin for the calibration drift curve. The drift curve indicates a number of corrections to be made to the sonic log. A list of shifts used on the sonic data is given below. The check level at 1157 metres below DF is lying 3 msec off the drift curve. Although the geophone stack for this level is good the drift indicated by this check level has not been followed and instead a more general drift has been applied.

Table 3

Depth Interval (m below DF)	Block Shift $\mu sec/m$	$\Delta t_{min} \ \mu sec/m$	Equiv Block Shift $\mu sec/m$
0-183	0	-	0
183-797.3	17.74		17.74
797.3-1202	9.39	-	9.39
1202-2234	0.48	-	0.48
2234-2634	_	223.55	-9.00
2634-2815	13.81	-	13.81

The adjusted sonic curve is considered to be the best result using the available data.

## **6.0 GEOGRAM PROCESSING**

Geograms were generated using 20,25,30 and 35hertz Ricker wavelets. The presentations include both normal and reverse polarity at 3.75in/sec.

Geogram processing produces synthetic seismic traces based on reflection coefficients generated from sonic and density measurements in the well-bore. The steps in the processing chain are the following:

Time to depth conversion Generate reflection coefficients Generate attenuation coefficients Choose a suitable wavelet Convolution Output.

# 6.1 Time to Depth Conversion

Open hole logs are recorded from the bottom to top with a depth index. This data is converted to a two-way time index and slipped to read from the top to bottom in order to match the seismic section.

## 6.2 Primary Reflection Coefficients

Sonic and density data are averaged over chosen time intervals (normally 2 or 4 millisecs). Reflection coefficients are then computed using:

$$R = \frac{\rho_2.\nu_2 - \rho_1.\nu_1}{\rho_2.\nu_2 + \rho_1.\nu_1}$$

where

 $\rho_1$  = density of the layer above the reflection interface

 $\rho_2$  = density of the layer below the reflection interface

 $\nu_1$  = compressional wave velocity of the layer above

the reflection interface

 $u_2$  = compressional wave velocity of the layer below the reflection interface

This computation is done for each time interval to generate a set of primary reflection coefficients without transmission losses.

#### 6.3 Primaries with Transmission Loss

Transmission loss on two-way attenuation coefficients are computed using:

$$A_n = (1 - R_1^2).(1 - R_2^2).(1 - R_3^2)...(1 - R_n^2)$$

A set of primary reflection coefficients with transmission loss is generated using:

$$Primary_n = R_n.A_{n-1}$$

## 6.4 Primaries plus Multiples

Multiples are computed from these input reflection coefficients using the transform technique from the top of the well to obtain the impulse response of the earth. The transform outputs primaries plus multiples.

### 6.5 Multiples Only

By subtracting previously calculated primaries from the above result we obtain multiples only.

#### 6.6 Wavelet


A theoretical wavelet is chosen to use for convolution with the reflection coefficients previously generated. Choices available include:

Klauder wavelet Ricker zero phase wavelet Ricker minimum phase wavelet User defined wavelet.

All wavelets can be chosen with or without butterworth filtering and with user defined centre frequencies. Polarity conventions are shown in Figure 1. These Geograms were generated using zero and minimum phase ricker wavelets.

#### 6.7 Convolution

Standard procedure of convolution of wavelet with reflection coefficients. The output is the synthetic seismogram.




NOTE: WAVELET DISPLAYED UNDER GEOGRAMS ARE FOR A REFLECTION COEFFICIENT OF -0.5

FIGURE 1

Schlu	mberger		WELL	SEISMIC	SERVICE	FIE	ELD RE	PORT	
СОМР	ANY	WELL	DA	TE	LOCATION	ENGINE	ER	WITNESSED BY	
ESSO	AUST.	WHIPTA	IL#1A 28/	8/85	VEA	DAWSO	1	BARRETT	
<b>≅</b> T □	METRES	JACK PLATI	UP [ FORM [	_	.S∪8 <b>⊠</b>	WEATH	ER:		
SCHLU	MBERGER	ZERO DE	RILL FLOO	R AT	ELEVATION	20.7m		RELATIVE TO MEA	N SEA LEVEL (M.S.L.)
	EASURED F		DF		ELEVATION	O m			LUMBERGER ZERO
DAILLI	NG MEASUF	RED FROM	DF	AT	ELEVATION	O m	***************************************	RELATIVE TO SCH	LUMBERGER ZERO
		SOURCE				LINFORM		DISTANCE	HOUR DATE
		ATER [	AIR 🖸		TIDE LEVE				
	ME1X SURE _120_				(RECORD I MORE THA				
	TOR TYPE _				DURING SU				
	P LENGTH _			CONDS					
FROM	HZ	TO	HZ	•	CSU SOFT	WARE VE	RSION:	MAX. HOLE DE	V: 0° AZIM:
	NOTE: SH	IOTS HIGHL	Y RECOMM	ENDED AT T	D, TOP EACH	SONIC, A	BOVE AN	D BELOW BAD HOLE	
· · · · · · · · · · · · · · · · · · ·			•	UNC	CORRECTED	RESULTS	3	Quality: G = Good, P =	 Poor, U = Unsatisfactory
SHOT NO.	DEPTH	GUN PRESSURE	FILTERS	TRANSIT TIME	HOUR SHOT	FILE	STACK	STACKED SHOTS	QUALITY / REMARKS
	29.8 m		OFF	24.8	18:36		1	8.9.10	
	1126		OFF	464.0	19:35		1	1,2,5	
	2815	<u> </u>	OFF	939.3	20:47	16	1	4.5.6	
	2619 2456		OFF OFF	891.4 851.4	21:05	16 16	2	7,8,9	
	2312		OFF	817.5	21:20	16	<u>3</u> 4	10,11,12	
	2166		OFF	781.2	21:38	16	5	18,19,20	
	2002 ·		OFF	737.0	21:45	16	6	22 - 24	
	1867		OFF	702.2	21:49	16	7	25 - 27	
	1687		OFF	651.0	21:54	16	8	28,30,31	
	1525		OFF	604.9	22:05	16	9	36 - 38	
	1379		OFF	557.2	22:11	16	10	39,40,45	
	1203		OFF	494.6	22:16	16	11	47 - 49	
	1157		OFF	476.5	22:24	16	12	50, 51,53	
	1126		OFF	466.4	22:30	16	13	55,56,58,59	
	1126		OFF	466.4	22:33	16	14	60,62,63	
	967 800		OFF OFF	400.4 329.5	22:39	16 16	15 16	64,65,66 70 - 72	
	688		OFF	289.9	22:47	16	17	73 - 75	
	390		OFF	175.4	22:58	16	18	76 - 78	
	200		OFF	61.6	23:13	16	19	80, 81,83	
	1		1	}					
						F	ı		i .
		•							
		•							
		•							
		•							
		•							
		•							

# 5. GUN GEOMETRY SKETCH WHIPTAIL-1A



DWG. 2310/0P/3

# 6. CHECK SHOT DATA - OBSERVED AND CORRECTED

LEVEL NUMBER	MEASUR DEPTH FROM DF M	VERTIC DEPTH FROM SRD M	VERTIC DEPTH FROM GL M	OBSERV TRAVEL TIME HYD/GEO MS	VERTIC TRAVEL TIME SRC/GEO MS	VERTIC TRAVEL TIME SRD/GED MS	AVERAGE VELOC SRD/GEO M/S	DELTA DEPTH BETWEEN SHOTS M	DELTA TIME BETWEEN SHOTS MS	INTERV VELOC BETWEEN SHOTS M/S
1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16	59.70 183.03 390.00 688.00 800.00 967.00 1126.00 1157.00 1203.00 1379.00 1525.00 1687.00 2002.00 2166.00 2312.00 2456.00	39.00 162.33 369.30 667.30 779.30 946.30 1105.30 1136.30 1182.30 1358.30 1504.30 1666.30 1846.30 1981.30 2145.30 2291.30 2435.30	0 123.33 330.30 628.30 740.30 907.30 1066.30 1097.30 1143.30 1319.30 1465.30 1627.30 1807.30 1942.30 2106.30 2252.30 2396.30	32.14 85.20 175.00 288.00 328.00 398.00 465.00 475.00 493.00 556.00 602.00 649.00 700.00 735.00 777.00 814.00 848.00	20.20 82.82 174.08 287.55 327.62 397.69 464.74 474.74 492.76 555.79 601.82 648.84 699.86 734.87 776.88 813.89 847.90	26.35 88.97 180.23 293.69 333.77 403.84 470.88 480.89 498.90 561.94 607.96 654.99 706.01 741.02 783.03 820.04 854.05	1480 1825 2049 2272 2335 2343 2347 2363 2370 2417 2474 2544 2615 2674 2740 2794 2851	123.33 206.97 298.00 112.00 167.00 159.00 31.00 46.00 176.00 146.00 180.00 135.00 164.00 146.00	62.62 91.26 113.46 40.08 70.07 67.05 10.01 18.01 63.04 46.02 47.02 51.02 35.01 42.01 37.01 34.01 40.01	1970 2268 2626 2795 2383 2372 3097 2554 2792 3172 3445 3528 3856 3904 3945 4234 4074
18 19	2619.00 2815.00	2598.30 2794.30	2559,30 2755,30	938.00	887.91 937.92	894.06 944.07	2906 2960	196,00	50,01	3919

This is an enclosure indicator page. The enclosure PE601140 is enclosed within the container PE902377 at this location in this document.

The enclosure PE601140 has the following characteristics:

ITEM_BARCODE = PE601140
CONTAINER_BARCODE = PE902377

NAME = Seismic Calibration Log

BASIN = GIPPSLAND PERMIT = VIC/L1 TYPE = WELL

SUBTYPE = VELOCITY_CHART

DESCRIPTION = Seismic Calibration Log, Adjusted

Continuous Velocity Log, CPI, (enclosure from WCR vol.1) for

Whiptail-1

REMARKS =

DATE_CREATED = 11/10/85 DATE_RECEIVED = 27/03/86

 $W_NO = W915$ 

WELL_NAME = Whiptail-1A CONTRACTOR = SCHLUMBERGER

CLIENT_OP_CO = ESSO AUSTRALIA LTD

This is an enclosure indicator page. The enclosure PE601141 is enclosed within the container PE902377 at this location in this document.

The enclosure PE601141 has the following characteristics:

ITEM_BARCODE = PE601141
CONTAINER_BARCODE = PE902377

NAME = Seismic Calibration Log

BASIN = GIPPSLAND PERMIT = VIC/L1 TYPE = WELL

SUBTYPE = VELOCITY_CHART

DESCRIPTION = Seismic Calibration Log, Adjusted

continuous data, Perth Computing

Centre, (enclosure from WCR vol.1) for

Whiptail-1

REMARKS =

DATE_CREATED = 7/09/85 DATE_RECEIVED = 27/03/86

 $W_NO = W915$ 

WELL_NAME = Whiptail-1A CONTRACTOR = SCHLUMBERGER

CLIENT_OP_CO = ESSO AUSTRALIA LTD

This is an enclosure indicator page. The enclosure PE902378 is enclosed within the container PE902377 at this location in this document.

The enclosure PE902378 has the following characteristics:

ITEM_BARCODE = PE902378 CONTAINER_BARCODE = PE902377

NAME = Raw and Stacked Shots - Velocity check

shot survey

BASIN = GIPPSLAND

PERMIT = VIC/L1 TYPE = WELL

SUBTYPE = VELOCITY_CHART

DESCRIPTION = Raw and Stacked Shots - Velocity check

shot survey (enclosure from WCR vol.1)

for Whiptail-1

REMARKS =

 $DATE_CREATED = 11/10/85$ 

DATE_RECEIVED = 27/03/86

 $W_NO = W915$ 

WELL_NAME = Whiptail-1A CONTRACTOR = SCHLUMBERGER

CLIENT_OP_CO = ESSO AUSTRALIA LTD

This is an enclosure indicator page. The enclosure PE902379 is enclosed within the container PE902377 at this location in this document.

The enclosure PE902379 has the following characteristics:

ITEM_BARCODE = PE902379
CONTAINER_BARCODE = PE902377

NAME = Synthetic Seismogram - Geogram

BASIN = GIPPSLAND PERMIT = VIC/L1

TYPE = WELL SUBTYPE = SYNTH_SEISMOGRAM

DESCRIPTION = Synthetic Seismogram - Geogram

(enclosure from WCR vol.1) for

Whiptail-1

REMARKS =

DATE_CREATED = 7/09/85 DATE_RECEIVED = 27/03/86

 $W_NO = W915$ 

WELL_NAME = Whiptail-1A
CONTRACTOR = SCHLUMBERGER

CLIENT_OP_CO = ESSO AUSTRALIA LTD

This is an enclosure indicator page. The enclosure PE902380 is enclosed within the container PE902377 at this location in this document.

The enclosure PE902380 has the following characteristics:

ITEM_BARCODE = PE902380
CONTAINER_BARCODE = PE902377

NAME = Time Depth Curve

BASIN = GIPPSLAND PERMIT = VIC/L1 TYPE = WELL

SUBTYPE = VELOCITY_CHART

DESCRIPTION = Time Depth Curve (enclosure from WCR

vol.1) for Whiptail-1

REMARKS =

DATE_CREATED = 28/08/85 DATE_RECEIVED = 27/03/86

 $W_NO = W915$ 

WELL_NAME = Whiptail-1A

CONTRACTOR =

CLIENT_OP_CO = ESSO EXPLORATION AND PRODUCTION

AUSTRALIA LTD